


Construction division.  
Advice for giving credit to contractors/suppliers.

Sl. No. - site bills register		1056		Date - site bills Register		17-12-2021	
Company Name:		MPL		Site:		may flower platinum	
Name of Contractor		Janardhan Prasad					
Nature of work		Tiles laying					
Work done		From Date		To Date			
		1-12-2021		10-12-2021			
Sl. No.	Villa/Flat/block no.	Qty.	Rate	Units	Amount	Contractors bill no	
1.	corridor tiles						
2.	laying at 9 <sup>th</sup> floor - part-2						
3.	Flooring area	2.467	17	sft	41,939		
4.							
5.	cladding area	2.752	17	sft	46,784		
6.							
7.	making hole for	16	50	nos	800		
8.	lights camera						
9.							
10.							
11.	Total:				89,523=00		
Bill required		<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO.		GST bill required		YES <input checked="" type="checkbox"/> NO.	
Measurement & estimate sheet:		<input checked="" type="checkbox"/> Required <input type="checkbox"/> Not required		Measurement & estimate sheet:		<input checked="" type="checkbox"/> Enclosed <input type="checkbox"/> Not enclosed	
PO/WO no.				PO/WO date:			
Remarks :							
Approved by Project Manager		Approved by Design Team		Approved by M.D.			
Date: 7/12/2021		Date:		Date:			
Sign: 		Sign:		Sign:			

Notes: 1. This advice must be sent within 7 days of completing work. 2. This form can be used for certifying labour bills, bills for hire charges, earth work, turnkey civil contractors. 3. Wherever not applicable - fill NA. 4. Estimate and measurement sheets are not required for turnkey jobs where guideline rates are clearly given.

ESTIMATE SHEET							
Company Name:	MPL						
Project:	May Flower Platinum						
Work Description:	Corridor Tiles laying at 9th floor- part 2						
Contractor Name:	Janardhan Prasad						
prepared by:	K. Narendar Reddy						
Date:	17-12-2021						
S.No.	Item Head	Item Description	Quantity	Units	Rate	Amount	Grand Total
1	Corridor Tiles laying at 9th floor- part 2	Corridor floor tiles laying Flooring Area	2467.00	sft	17.00	41939.00	
2	Wall tiles cladding	Cladding Area	2752.00	sft	17.00	46784.00	
3	Making hole for light and	Making hole for light and camera	16.00	nos	50.00	800.00	
							<b>89523.00</b>
<b>Amount in words Eighty Nine Thousand Five Hundred and Twenty Three Rupees only</b>							
<b>Notre : We paid Rs.13/- + 4/- extra = 17/- per sft per big tiles</b>							

MEASUREMENT SHEET										
Company Name:		MPL								
Project:		May Flower Platinum								
Work Description:		Corridor Tiles laying at 9th floor- part 2								
Contractor Name:		Janardhan Prasad								
prepared by:		K Narendar Reddy								
Date:		17-12-2021								
S.No	Item Head	Item Description	A Length	B Width	C Height	D Nos.	E Quantity	F Units	G Total Head sft	
1	Corridor Tiles laying at 9th floor- part 2 Corridor Big tiles laying - Flooring	Flooring area	50.00	7.00	1.00	1	350.00	sft		
		B4 flat opp	64.00	9.00	1.00	1	576.00	sft		
		B3 flat opp	42.50	7.00	1.00	1	297.50	sft		
		C6 opp	45.00	17.33	1.00	1	779.85	sft		
		C4 opp	45.00	6.75	1.00	1	303.75	sft		
		C2 to C3 flats staircase	16.00	10.00	1.00	1	160.00	sft		
		Total Flooring Area						2467		
		Walls cladding	50.00	1.00	4.00	2	400.00	sft		
		B4 flat to B3 flat	64.00	1.00	4.00	2	512.00	sft		
		B3 to C6 flat	42.50	1.00	4.00	2	340.00	sft		
C6 to C5 flat	17.00	1.00	4.00	2	136.00	sft				
C1 to C4	45.00	1.00	4.00	2	360.00	sft				
C2 to C3	10.00	1.00	4.00	2	80.00	sft				
Electrical ducts	10.75	9.00	1.00	2	193.50	sft				
Main Doors	8.00	1.00	8.50	8	544.00	sft				
VRF AC window	10.00	1.00	8.50	4	340.00	sft				
		Deduction								
		Doors	3.50	1.00	7.00	8	196.00	sft		
		Doors	3.50	1.00	4.00	8	112.00	sft		
		VRF AC Window	6.00	1.00	6.00	4	144.00	sft		
		Doors	5.50	1.00	4.00	1	22.00	sft		
		Doors	2.00	1.00	5.00	4	40.00	sft		
		Total Wall Cladding Area					514			
							2752			
3	Making hole for light and camera	Making hole for light and camera	16.00	1.00	1.00	1	16.00	nos		

**Bill for Consumables**

Janardhan  
Kakatiya nagar, Neeredmet  
Hyderabad

Date: 17-12-2021

**In favor of:** MPL  
**Project / Site:** MFPP  
**Location:** 82/1. Mallapur  
**Type of Work:** Corridor Tiles laying at 9th floor- part 2  
**Towards:** Allowance for Consumables

S No.	Description	Amount
1.	Brief description of work done Corridor Tiles laying at 9th floor- part 2 Total amount =Rs 89523=00 Work done from date 01-12-2021 to 10-12-2021	Rs.17905=00

Amount in words: Seventeen Thousand Nine Hundred and Five rupees only.

Sign: \_\_\_\_\_

**Bill for Labour charges**

Janardhan  
Kakatiya nagar, Neeredmet  
Hyderabad

Date:17-12-2021

**In favor of:** MPL  
**Project / Site:** MFPP  
**Location:** 82/1. Mallapur  
**Type of Work:** Corridor Tiles laying at 9th floor- part 2  
**Towards:** Allowance for Labour charges

S No.	Description	Amount
1.	Brief description of work done Corridor Tiles laying at 9th floor- part 2 Total amount =Rs 89523=00 Work done from date 01-12-2021 to 10-12-2021	Rs.35809=00

Amount in words: Thirty Five Thousand Eight Hundred and Nine rupees only.

Sign: \_\_\_\_\_

**Bill for Equipment Allowance**

Janardhan  
Kakatiya nagar, Neeredmet  
Hyderabad

Date:17-12-2021

**In favor of:** MPL  
**Project / Site:** MFPP  
**Location:** 82/1. Mallapur  
**Type of Work:** Corridor Tiles laying at 9th floor- part 2  
**Towards:** Allowance for Equipment

S No.	Description	Amount
1.	Brief description of work done Corridor Tiles laying at 9th floor- part 2 Total amount =Rs 89523=00 Work done from date 01-12-2021 to 10-12-2021	Rs.35809=00

Amount in words: Thirty Five Thousand Eight Hundred and Nine rupees only.

Sign: \_\_\_\_\_