

Construction division.
Advice for giving credit to contractors/suppliers.

Sl. No. - site bills register		190	Date - site bills Register		17/01/24	
Company Name:		Dr. NPK Big Tech Pvt Ltd		Site:		
Name of Contractor		Narsing Rao				
Nature of work		Main block - NE, NW - Staircase putty + ORB, ceiling, H.P. walls				
Work done		From Date		To Date		
Sl. No.	Villa/Flat/block no.	Qty.	Rate	Units	Amount	Contractors bill no
①	1. M.B - staircase putty	400	11.75	8FT	4,701/-	
	2. +ORB - NE - H.P					
	3. walls + ceiling					
②	4. NW - H.P walls +	400	11.75	8FT	4,701/-	
	5. ceiling					
③	6. Primer - lifts,	12934	1.75	8FT	22,635/-	
	7. ducts, DWP					
	8.					
	9.					
	10.					
11.	Total:				32036/-	
Bill required		<input type="checkbox"/> YES <input type="checkbox"/> NO.		GST bill required		<input type="checkbox"/> YES <input type="checkbox"/> NO.
Measurement & estimate sheet:		<input type="checkbox"/> Required <input type="checkbox"/> Not required		Measurement & estimate sheet:		<input type="checkbox"/> Enclosed <input type="checkbox"/> Not enclosed
PO/WO no.				PO/WO date:		
Remarks : -As per circular no - 844 (F)						
Approved by Project Manager		Approved by Design Team		Approved by M.D.		
Date:		Date:		Date:		
Sign:		Sign:		Sign:		

Notes: 1. This advice must be sent within 7 days of completing work. 2. This form can be used for certifying labour bills, bills for hire charges, earth work, turnkey civil contractors. 3. Wherever not applicable - fill NA. 4. Estimate and measurement sheets are not required for turnkey jobs where guideline rates are clearly given.

RAM KISHAN
PROJECT MANAGER

ESTIMATE SHEET

Company Name: DR Nrk biotech Pvt ltd
 Project: Nextopolis
 Work Description: Main block
 Contractor Name: Narsing Rao
 Prepared By: Sai kumar
 Date: 17.01.2024

Approved by: 
 Sign: Ramkishan

(Sl. No. 1 + \$1. No. 6)
 (5.75 + 2.00 = 7.75)

S No.	Item Head	Item Description	Quantity	Units	Rate	Amount
1	Main block	Staircase Putty + OBD				
	Northeast	Headroom walls + Ceiling	400	Sft	11.75	4,701
	NorthWest	Headroom walls + Ceiling	400	Sft	11.75	4,701
	Primer	Lifts, ducts, Rwp	12934	Sft	1.75	22,635
		Total				32036.0

Circular no-844 (F) dated 19.10.21

Inwords:-Thirty two thousand thirty six only.

MEASUREMENT SHEET

Company Name: DR Nrk biotech Pvt ltd
 Project: Nextopolis
 Work Description: Main block ✓
 Contractor Name: Narsing Rao ✓
 Prepared By: Sai kumar ✓
 Date: 17.01.24 ✓

Approved by:
 Sign: 

Ramkishan

S No.	Item Head	Item Description	A Length	B Width	C Height	D Nos	E= AxBxCxD Quantity	F Units
1	Main block	Staircase Putty + OBD						
	Northeast	Headroom walls + Ceiling	28.58 ✓	14.00 ✓	1.00	1.00	400.12 ✓	Sft
	NorthWest	Headroom walls + Ceiling	28.58 ✓	14.00 ✓	1.00	1.00	400.12 ✓	Sft
	Northeast lift 5	Primer	27.00 ✓	1.00 ✓	81.83 ✓	2.00 ✓	4418.82 ✓	Sft
	NorthWest lift 5	Primer	27.00 ✓	1.00 ✓	81.83 ✓	2.00 ✓	4418.82 ✓	Sft
	SouthEast Fire duct	Primer	17.58 ✓	1.00 ✓	48.25 ✓	1.00 ✓	848.24 ✓	sft
	SouthWest Fire duct	Primer	17.58 ✓	1.00 ✓	48.25 ✓	1.00 ✓	848.24 ✓	sft
	Northwest rainwater	Primer	20.00 ✓	1.00 ✓	60.00 ✓	1.00 ✓	1200.00 ✓	sft
	NorthEast rainwater	Primer	20.00 ✓	1.00 ✓	60.00 ✓	1.00 ✓	1200.00 ✓	sft
						Total:	12934.11	sft