

Estimation Of Painting Work & Marble Skirting at Soham Mansion							
S.No	Description	Length	Breadth	Area(sft)	Rate	Amount	Remarks
1	<b>III Floor @ MPIPL</b>	9.50	11.25	106.88			Wall Area
2	Wall (2 sides)	6.00	11.25	135.00			
3	Wall	11.83	8.25	97.62			
4	Wall	16.42	11.50	188.78			
5	Wall	12.50	9.50	118.75			
6	Wall	17.17	11.33	194.49			
7	Wall	11.33	17.00	192.61			
8	Wall	9.25	4.50	41.63			
9	Wall	9.25	5.17	47.79			
10	Wall	9.25	2.50	23.13			
11	Railing(2 sides)	10.00	4.00	80.00			
12	Railing(2 sides)	15.66	4.00	125.28			
				1,351.95	5.50	Rs.7,435.67	2 -Coats of Lappam & 1-coat of Paint
	<b>III Floor @ Ranbaxy</b>						
1	Wall	72.50	11.00	797.50			
2	Ceiling	18.66	9.00	167.94			
3	Beam Portion	9.00	3.00	27.00			
4	Beam Portion	9.00	6.00	54.00			
5	Stair Case Ceiling	10.00	4.00	40.00			
6	Railing(2 sides)	20.66	4.00	165.28			
				1,251.72	5.50	Rs6,884.46	
	<b>II Floor</b>						
1	Wall	8.50	11.00	93.50			
2	Ceiling	9.17	5.00	45.83			
3	Wall	16.00	11.00	176.00			
4	Ceiling	25.83	4.50	116.25			
5	Wall	12.00	3.00	36.00			
6	Wall	47.50	11.00	522.50			
7	Wall	6.00	11.00	66.00			
8	Wall	22.25	11.00	244.75			
	<b>At Luharika</b>						
9	Ceiling	21.17	4.50	95.25			
10	Wall	21.17	11.00	232.83			
11	Wall	26.17	12.00	313.99			
12	Wall	11.25	3.00	33.75			
13	Wall	12.00	4.00	48.00			
14	Railing (2-sides)	21.00	4.00	168.00			
15	Railing(2 sides)	10.50	4.00	84.00			
				2,276.64	5.50	Rs.12,520.97	
S.No	Description	Length	Breadth	Area(sft)	Rate	Amount	Remarks
	<b>I Floor</b>						
1	Wall	60.83	11.00	669.16			
	<b>At EPEC</b>						
2	Ceiling	18.50	9.17	169.57			
3	Wall	4.00	11.00	44.00			
4	Beam Portion	9.17	4.00	36.66			
5	Wall	4.00	11.00	44.00			
6	Wall	6.33	3.17	20.04			
7	Wall	5.75	4.50	25.88			
8	Beam Portion	9.17	3.00	27.50			
9	Beam Portion	9.17	2.00	18.33			
10	Beam Portion	10.17	3.00	30.50			
11	Wall	15.00	11.00	165.00			
12	Wall	9.00	8.00	72.00			
13	Wall	13.00	12.00	156.00			
14	Railing(2-sides)	19.00	4.00	152.00			
				1,630.64	5.50	Rs.8,968.2	
	<b>Ground Floor</b>						
1	Wall	12.58	11.00	138.41			
2	Wall	14.75	12.00	177.00			
3	Ceiling	9.00	10.33	92.97			
4	Beam Portion	9.00	2.00	18.00			
5	Wall	4.00	2.00	8.00			
6	Railing	18.00	4.00	72.00			
7	Wall	14.00	8.00	112.00			
				618.38	5.50	Rs.3,401.9	
	<b>Total Amount</b>					<b>Rs.39,209</b>	

	<b>Estimation Of 3" Marble Skirting</b>						
		Area(rft)					
1	Ground Floor	91.99					
2	First floor	70.58					
3	Second Floor	54.17					
4	II Floor(at Luharika)	44.00					
5	III Floor	110.50					
	<b>Total Area(Rft)</b>	<b>371.25 @ Rs 25rft (Incl.Of Material &amp; Labour)</b>	<b>Rs.9281.25</b>				
				<b>Total Amount</b>	<b>48,490.25</b>		