

CENTRAL POWER DISTRIBUTION COMPANY OF ANDHRA PRADESH LIMITED

From

To

The Superintending Engineer  
Operation, RR East Circle,  
Habsiguda, Hyderabad.

M/s. Mehta and Modi Homes,  
Sy. No: 74 & 75, Cherlapally.

Lr.No.SE/Op/RREast/Comm/D.No. 3348 /12 Dt. 12.03 .2013

Sir,

Sub : Electy – APCPDCL – Op – RR East- Extension for extension of supply to 1 No 3-Ph 20 KW Domestic load and 44 Nos. each 5 KWs Domestic load over and above the existing 1 No. 5 KW non-Domestic load (Sc. No: 2209-04747 to M/s. Mehta and Modi Homes at Sy. No: 74 & 75, Cherlapally Section of Sainikpuri sub Division in Sainikpuri Division in RR East Circle - Estimate sanctioned – Permission for supply of materials and for execution of works by yourself on turn key basis – Accorded – Regarding.

Ref : 1. Memo. No: CGM/Operation/RRZone/Hyd/DE(T)/ADE-I/D. No: 5054/12-13, Dt: 05.03.2013  
2. Consumer representation dated : 07.03.2013

Under the circumstances explained above your letter 2nd cited and you are permitted to supply the materials COMPLETELY & EXECUTE the works in respect of the scheme sanctioned under reference 1<sup>st</sup> cited, with the following details :

- a) Erection of 11 KV line with 55 Sqmm AAA Conductor for a distance of 0.28 Km over 9.1 Mtrs. PSCC pole.
- b) Erection of HT Switch Gear, SP Structure and Column type plinth.
- c) Laying of LT 3 ½ core 70 Sq. mm XLPE UG Cable for a distance of 480 Mtrs.
- d) Laying of LT 3 ½ corer 185 Sq. mm XLPE UG cable for a distance of 20 Mtrs.
- e) Laying of LT 1 x 120 SQ. mm Sq. mm XLPE UG cable for a distance of 40 Mtrs.
- f) Erection of 1 No. 160 KVA DTR supplied by APCPDCL.
- g) Erection of 4 Nos. feeder pillar boxes and 2 Nos. Control Panels.
- h) To Effect the release of supply to 1 No 3-Ph 20 KW Domestic load and 44 Nos. each 5 KWs Domestic load.

The permission now accorded is subject to the following conditions.

1. A licensed electrical contractor under the supervision of the APCPDCL's Officials, etc., should execute the works.
2. The materials used in the works should confirm to APCPDCL's Specification.
3. If any unforeseen calamities / Accidents occur during the execution of the above work the APCPDCL authorities are not held responsible for such incidents and consequential losses or damages.
4. Major materials like distribution transformers, A.B. Switches, H.G. Fuse. Sets, conductor, structural steel and other materials except insulators should be purchased as per APCPDCL Standard Specifications along with test certificates from CPDCL vendors. The bills/vouchers of materials purchased along with TCs should be produced to **Divisional Engineer/Operation/Sainikpuri** before executing of work.
5. You should hand over all the works executed by you to the APCPDCL's Officials after completion in full shape. The work executed by you shall be taken over the APCPDCL after statutory inspection of APCPDCL's Officials. The installation shall be deemed to be the property of APCPDCL's after such take over. The proposed Distribution Transformer, L.T. Lines should be out side of consumer premises only.
6. The consumer should provide sealing arrangement for control panel and metering equipment.
7. The proposed power to the premises should not have 2<sup>nd</sup> service / arrears to be paid and no court case pending.
8. The proposed Distribution Transformer LT Lines should be out side of consumer premises only.
9. There should not be any 11 KV/ LT Lines passing through from other source of supply in the proposed premises.
10. Furnish approval of CEIG for your Electrical Installation.

11. Furnish NOC from AP Pollution control Board.
12. To pay 10% of the estimate cost, cost of the Distribution Transformer, cost of insulators, difference development charges and Security deposit of Rs. **3,83,770/- (Rupees Three lakhs eighty three thousand seven hundred and seventy only)** in the form of Demand Draft in favour of **APCPDCL /Hyderabad** and handed over the DD at **Customer Service Centre, Sainikpuri**.
13. It is the responsibility of the developer for any loss of material utilized in completing the work till all the services contemplated in the proposal are released.
14. The **Divisional Engineer/Operation/ Sainikpuri** should inspect the work before charging the equipment and ensure whether and quality and quantity of work is carried out as per the estimate sanction and as per the APCPDCL standards.

You may contact **Divisional Engineer/Operation/ Sainikpuri** for further in this matter.

Payable amount on Turnkey		
a)	10% Incidental charges on estimate cost	78076.00
b)	Cost of Insulators	7383.61
c)	Cost of Distribution Transformer	182152.64
d)	Difference Developmental Charges (DC - DTR)	68157.89
e)	Security Deposit	48000.00
	Total	383770.14
	Or Say	383770.00

Or Say Rs. **3,83,770/- (Rupees Three lakhs eighty three thousand seven hundred and seventy only)**

**Note:** Before making above payments you are requested to contact **Divisional Engineer/ Operation/ Sainikpuri** as the consumer has to comply with other requirements to be dealt at field level and also other procedures as detailed below:

- a) Obtaining CEIG/CEA Approval for electrical installation.
- b) Obtaining NOC as per the requirement of the A.P. Fire Services Act, 1999, Multi-storied building regulations. The Municipal Corporation building by-laws, 1981.
- c) No service connection shall be issued to multistoried buildings / complexes greater than 10Mtrs in height unless occupancy certificate from MCH is to be submitted.

The Assistant Divisional Engineer/Op/ Sainikpuri is requested to follow the proceedings issued by the District Collector vide Proc. No. Collr/SPI/RR/2007, dated 25.10.2007 without fail.

Yours faithfully,

Sd/-  
SUPERINTENDING ENGINEER  
Operation : Ranga Reddy East: Hyderabad

Copy Submitted to : The Chief General Manager/ Commercial/ APCPDCL/ Hyd.  
Copy to : The Divisional Engineer /MRT/RR East /Hyderabad  
Copy to : The Divisional Engineer/Op/ Sainikpuri  
Copy to : The Asst. Divisional Engineer/Op/ Sainikpuri  
Copy to :The Asst. Engineer/Op/ Cherlapally.

// Forwarded :: By Order //

Asst.Divisional Engineer (Comm)  
Operation: RR East Circle, Hyderabad

**STATEMENT FOR SERVICE LINE CHARGES AND DEVELOPMENT CHARGES**

Extension for extension of supply to 1 No 3-Ph 20 KW Domestic load and 44 Nos. each 5 KWs Domestic load over and above the existing 1 No. 5 KW non-Domestic load (Sc. No: 2209-04747 to M/s. Mehta and Modi Homes at Sy. No: 74 & 75, Cherlapally Section of Sainikpuri sub Division in Sainikpuri Division in RR East Circle

Sl. No.	Description	Units	Qty	Rate	Amount in Rs.
I	<b>Total Cost of the Estimate</b>				<b>780760.00</b>
a)	Less cost of 1 No. 160 KVA DTR	No.	1	171842.11	171842.11
	Distribution Transformer				
b)	Less cost of				
	LT Trivector Meter	Nos.	1	5526	5526
	GPRS Modem with Sim	Nos.	1	4357	4357
	LT TVR meter	Nos.	1	6525	6525
	a)3-Ph 10-40 A Energy meters without P.P Box	Nos.	44	1836	80784
II	<b>Total Expenditure chargeable to CPDCL</b>				<b>269034.11</b>
				<b>orsay</b>	<b>269034.00</b>
III	<b>Service line charges to be collected</b>				<b>511726.00</b>
IV	<b>Development charges to be collected</b>	<b>Services</b>	<b>Nos.</b>	<b>Load in KW</b>	<b>Dev. Charges</b>
a)	Domestic @ Rs. 1000/- per KW	3-Phase	44	5	220000
		3-Phase	1	20	20000
				<b>Total</b>	<b>240000.00</b>
V	<b>Security deposit charges to be collected</b>	<b>Services</b>	<b>Nos.</b>	<b>Load in KW</b>	<b>S.D. Charges</b>
a)	Domestic @ Rs. 200/- per KW	3 phase	44	5	44000.00
		3 phase	1	20	4000.00
				<b>Total</b>	<b>48000.00</b>
	<b>Payable amount on Turnkey</b>				
a)	10% Incidental charges on estimate cost				<b>78076.00</b>
b)	Cost of Insulators				<b>7383.61</b>
c)	Cost of Distribution Transformer				<b>182152.64</b>
d)	Difference Developmental Charges (DC - DTR)				<b>68157.89</b>
e)	Security Deposit				<b>48000.00</b>
	<b>Total</b>				<b>383770.14</b>
					<b>Or Say 383770.00</b>

sd/-

**Superintending Engineer  
Operation::RR East Circle**

// Forwarded :: By Order //

  
**Asst. Divisional Engineer (CommI)  
Operation: RR East Circle, Hyderabad**

