Office of THE CHIEF GENERAL MANAGER COMMERCIAL CORPORATE OFFICE HYDERARAD

SPOO(COMMERCIAL)/MS.NO.1364/2022-23.DATED:12.10.2022

Sub:-

TSSPDCL - COMML - Estimate for extension of supply to 119Nos.3-Ph each 5KW Domestic loads,1No. 3-Ph 15KW Domestic Load (Common Purpose) and 1No. 3-Ph each 15KW Non-Domestic load (Club House Purpose) over and above the existing 1No.3-Ph 27KW LT Categor y-VIII load (SC.No.TS23 00005) making a total load of 652KW to M/s.Mehta & Modi Realty at Sy.No.196, Yapral Section of Sainikpuri Sub-Division in Village in Sainikpuri Habsiguda circle under Capital Works - Sanction - Administra tive approval accorded - Reg. Division

Ref: Estimate Number:

E-2022-14-03-11-03-028

The above estimate is administratively approved and technically sanctioned and registered as C.NO.475977, NOTE NO#17, DATED:10.10.2022

The sanction accords is subject to the follwing conditions:

- 1. TSSPDCL after careful examination of the above proposal hereby accords approval for the scheme at a cost of 43,65,114.27
- 2. In excercise of the powers conferred under section 42.1 of the Electricity Act, 2003 Central Act. No.36 of 2003 it system in his area of supply and to supply electricity in accordance with the provisions contained in this act.
- 3. The sanction accorded in para-1 above is subject to instructions issued already on release of service and tariff as may be in force from time to time.
- 4. The expenditure is chargeable to TSSPDCL-Capital Receipts and Expenditure- B, Expenditure-2 Transmission Lines (Including Sub-Stations) 3 Distribution System (Including Sub-Stations) capital works in progress Transmission plant (Extra High Voltage A/C. No.0204) Distribution System (High Voltage A/C. No.0204) Distribution System Medium Voltage (A/C. No.0206) Street Lighting.
 - THE ASSISTANT DIVISIONAL ENGINEER OPERATION SAINIKPURI SUB-DIVISION 5. The work will be executed by and all necessary approvals and payments must be ensured before release of supply.
 - 6. Consumer has to pay the following charges through a single DD in the Customer Service Center / Integrated Customer Service Center.

| Serviceline charges | Rs. | 21,19,636.91 |
|-----------------------------|---------|--------------|
| Development charges / DTR C | ost Rs. | 19,26,600.88 |
| CGST on Development Char | ges Rs. | 0.00 |
| SGST on Development Charg | ges Rs. | 0.00 |
| Initial Consumption Deposit | Rs. | 1,34,000.00 |
| Application Fee | Rs. | 0.00 |
| CGST on Application Fee | Rs. | 0.00 |
| SGST on Application Fee | Rs. | 0.00 |
| PTR Cost | Rs. | 0.00 |

Total Amount

Rs. 41,80,238,00

SD/-

DIRECTOR COMMERCIAL

Copy To:

THE ASSISTANTENGINEER/OPR/AE YAPRAL

THE ASSISTANT DIVISIONAL ENGINEER/OPERATION/SAINIKPURI SUB-DIVISION

THE DIVISION ALENGINEER/OPERATION/SAINIKPURI DIVISION

THE SUPERINTENDING ENGINEER/OPERATION/HABSIGUDA CIRCLE

THE CHIEF GENERAL MANAGER/OPERATION/MEDCHAL ZONE

Generated on 13-10-2022 11:26:28 in CGM_COMML logi

DIVISIONAL ENGINEER (Commercial), TSSPDCL, Corporate Office, 6-1-50, Compound Hyd-500 063



IM, E CHIEF GENERAL MANAGER MMERCIAL RPORATE OFFICE SPDCL DERABAD To, M/S MEHTA & MODI REALTY KOWKUR SY NO-196 KOWKUR MALKAJGIRI KOWKUR VILLAGE

?.NO.CGM(COMML)/SE(C)/DE(C)/ADE-IV/AE-I/D.NO.559/22, DT.12.10.022

TSSPDCI COMML Estimate for extension of supply 119Nos.3-Ph to each 5KW Domestic loads,1 No. 3-Ph 15KW Domestic Load (Common Purpose) and 1No. 3-Ph each 27KW LT 15KW Non-Domestic load (Club House Purpose) over and existing above the 1No 3-Ph Categor y-VIII load (SC.No.TS23 00005) making a total load of 652KW M/s.Mehta to & Modi Realty Sy.No.196, in Village Kowkoor Yapral Section Sainikpuri of Sub-Division in Sainikpuri Division of circle under Capital Works Sanction Administra tive accorded Demand Notice - Issued.

No: SPOO(COMMERCIAL)/MS.NO.1364/2022-23.DATED:12.10.2022

Estimate Number: E-2022-14-03-11-03-028

e permission accorded is subjected to the following conditions:

The work should be executed by a Licensed Contractor as per the standards of TSSPDCL under supervision of

THE ASSISTANT DIVISIONAL ENGINEER OPERATION SAINIKPURI SUB-DIVISION.

The material used in the work should confirm to TSSPDCL specifications.

If unforeseen calamities/ accidents occur during the execution of work, the TSSPDCL authorities are not held responsible for such incidents and consequential losses or damages. It is the responsibility of the consumer for any loss of material utilised in completing the work till all the services contemplated in the proposal are released.

Major materials like AB Switches, HG Fuse sets, Conductor, Structure steel and other materials should be purchased as per TSSPDCL specifications along with test certificate from TSSPDCL vendor. The bills/voucher of materials purchased along with test certificate should be produced to concerned CSC/ICSC before execution of work.

The work will be executed as per the sketch enclosed. The work executed by consumer shall be taken over by the TSSPDCL after statuary TSSPDCL after statuary inspection of TSSPDCL officials. The installation shall be deemed to the property of

TSSPDCL after such takeover.

The consumer should provide sealing arrangement for control panel and metering equipment.

The consumer shall clear off the dues of UDC/Bill stopped services if any existing in the premises or found at a later date and no court cases pending. If any legal disputes arise electricity supply will be disconnected to the premises.

There should not be any 11 KV /LT lines passing through from other source of supply in the proposed premises. Distribution Transformer will be provided by the TSSPDCL by collecting the cost of DTR/Development charges whichever is higher...

Obtaining CEIG/CEA approval for electrical installing. Obtaining NOC as per requirement of A.P Fire Services act 1999, Multi-storied building regulations.

No service connection shall be released for Multi-storied buildings / Complexes greater than 10Mtrs in height unless

occupancy certificate from concerned authorities.

You are requested to pay an Amount Rs.2909653.00 using the below available options:

a) In shape of Demand Draft in the Customer Service center / Integrated Customer Service drawn in favour of TSSPDCL Payable at HYDERABAD and handed over to In charge of C.S.Center/Integrated CS.Center.center.

(OR)
b) By scanning the QR Code using TSSPDCL App

(OR)

c) Through web portal - www.tssouthernpower.com,
Go To "Payment against Estimates" option and give Registration
number as input.
(In case of Estimate with multiple Registrations, Give any one
registration as input)

D.D must be received to concerned CSC within

60 days from D.D issue date.

Payments must be received before 11-01-2023, If not received existing registration will be cancelled. Work must be completed before 11-04-2023,

If not completed you have to forfeit the already paid amount.

DIVISIONAL ENGINEER (Commercial), TSSPDCL, Corporate Office, 6-1-50,

Mint Compound Hyd-500 063

| MITHERN |
|-------------------|
| THE WALLE MIL MAN |
| UTHERN |

| Description of Demand | Original Demand Notice Amount (In Rs) | Paid Amount 0 | To be paid Am (In Rs) |
|------------------------------------|---|---------------|--------------------------|
| Supervision Charges | 419,090.68 | 0 | 419,090.68 |
| CGST on Supervision charges | 37,718.16 | 0 | 37,718.16 |
| SGST on Supervision charges | 37,718.16 | 0 | 37,718.16 |
| Security Deposit | 134,000 | 0 | 134,000 |
| Material Cost | 203,699.25 | 0 | 203,699.25 |
| Material Cost Storage and Handling | 6,110.98 | 0 | 6,110.98 |
| CGST on Material Cost S&H | 549.99 | 0 | 549.99 |
| SGST on Material Cost S&H | 549.99 | 0 | 549.99 |
| Material Cost Contengencies | 6,110.98 | 0 | 6,110.98 |
| CGST on Material Contg Charges | 549.99 | C | 549.99 |
| SGST on Material Contg Charges | 549.99 | C | |
| DTR Cost | 1,926,600.88 | | |
| DTR SnH Charges | 57,798.03 | 3 | |
| CGST on DTR S&H Charges | 5,201.82 | 2 | |
| SGST on DTR SnH Charges | 5,201.82 | 2 | |
| DTR Contengencies Charges | 57,798.03 | 3 | 57,798.03 |
| CGST on DTR Contg Charges | 5,201.82 | 2 | 5,201.82 |
| SGST on DTR Contg Charges | 5,201.82 | 2 . | 5,201.82 |
| Rounded-off cost | 0.6 | 1 | 0.61 |
| Total Cost | 2,909,65 | 3 | 0 2,909,653 |

Note:

** In Case DTR is procured by Consumer and total DTR cost is greater than DC, niether DC nor DTR Cost will be collected.

** In Case DTR is procured by consumer is collected as Performance Security Charges. This amount along with Testing charges is to be collected and DD/BG

** 10% of cost for DTRs procured by consumer is collected as Performance Security Charges. This amount along with Testing charges is to be collected and DD/BG

details are to be entered in SAP while releasing the Estimate in JAO login.

** For works to be executed by Department, DTR is supplied by the Department and no Performance Security Deposit shall be collected.

** Testing charges of Rupees One thousand one hundred and eighty (i.e. Rs 1000 + 18 % GST) is to be collected.

**Application Fee of Rs. 3050.00 and GST (CGST Rs. 274.50 , SGST Rs. 274.50 paid at the time of registration.)

**You can pay through QR code Scanner or through RTGS to the following Accounts: Account No. 62169730364, Bank Name - SBI BANK, HABSIGUDA IFSC Code
**SBIN0020087

SD/-

DRECTOR COMMERCIAL



(Commercial), TSSPDCL, Corporate Office, 6-1-50, 19 Mint Compound Hyd-500 063

Estimate Cost Calculation Sheet

WBS Element

: E-2022-14-03-11-03-028

WBS Desc.:

M/s Mehta & Modi Realty at Sy.No:- 196,

Work Executed by

: CONSUMER

Service Connection Estimate

: NO

Estimate Plan Cost

: 43,65,114.27

| CSC Registration Number | Applicant Name | HT/ LT | Cat. | Sub- cat. / Volt. | \$ 1000 \$ | Cat. | | Mont | All Doc. Receiv | No of Shifts | : FXST load | Exst. Cat |
|----------------------------|--------------------------------|-----------|------|-------------------------|--|------|--------|------|-----------------------|-----------------|-------------|--------------|
| LTM222240064 | M/S MEHTA & MODI REALTY KOWKUR | LT | 01 | | 610,000 | 02 | 15,000 | | X | | | |

SD Calculation:

| CSC Registration Number | Cat. | Cont. load | Tariff S.D | Tariff D.C | Cat. | Cont. load | Tariff S.D | Tariff D.C | No. of Times S.D | No of Shifts | S.D Charges | Develo Cha |
|----------------------------|------|------------|------------|------------|------|------------|------------|------------|---------------------|-----------------|-------------|---------------|
| LTM222240064 | 01 | 610,000 | 0200 | 1200 | 02 | 15,000 | 0800 | 1200 | 1 | - | 134,000 | 750,000 |
| Total | 00 | 0 | | | | | | - | | | 134,000 | 750,000 |

DC Calculation / DTR:

New DTR Cost :

19,26,600.88

Final DTR Cost:

19,26,600.88

DC as per Load(incl GST):

8,85,000.00

Final Dev. Charges :

0.00

Materials to be issued by TSSPDCL:

| SI. No. | Material | Material Description | Quantity | Total Cost |
|---------|----------|--|----------|------------|
| 1 | MTE30026 | LT TVR Meters (4 CTs-0.5S)-DLMS protocol | 4 | 2: |
| 2 | CAH00178 | GPRS Modem | 4 | |
| 3 | TLE10045 | Sim Card | 4 | |
| 4 | MTE30038 | 3ph 10-40A Electronic IRDA port in PPBox | 119 | |
| 5 | MTE30040 | LT TVR 100/5A PP 0.5S (CAT-C) DLMS&IRDA | 2 | |
| 6 | DTC30127 | 3-Ph 315KVA Cu Wnd DTR BIS EEL2 Str-2 | 2 | 1.926 |

SLC (Refundable Deposit)/ Materials issued from Stores as per the payments to be made by the Customer (including 6%):

| SI. No | Material | Material Description | Quantity | Unit Price | Total |
|--------|-----------------|--|----------|------------|--------|
| 1 | CBX10007 | 11KV XLPE Cable 3 Core 185 Sq. mm | 115 | 1,200.33 | 100011 |
| 2 | CBX00004 | LT XLPE Cable 1 Core 120 Sq. mm | 40 | 145.14 | |
| 3 | INS10009 | 11KV Polymer Pin Insulators with GI pins | 15 | 209.98 | |
| 4 | HWR00002 | 11KV Metal parts(C&T) | 15 | 121.84 | |
| 5 | CDR00003 | AAA conductor 55 Sq. mm | 750 | 1/69.00 | |
| 6 | INS10003 | 11KV Polymer Insulators (C&T) | 15 | 208.56 | |
| | Total | 7 | | 7 200.50 | |
| | 3% S&H Ch. | 3% Storage & Handling Charges | | | |
| | 3% Contgs. | 3% Contingencies | | | |
| | G.Total | | | | |
| | 9% CGST-S&H Ch. | 9% CGST on Storage & Handling Charges | | | |
| | 9% SGST-S&H Ch. | 9% SGST on Storage & Handling Charges | | | |
| | ℃ CGST-Cont. | 9% CGST on Contingencies | | | |
| 7 | T-S&H Ch. | 9% SGST on Contingencies | | | |

Calculation:

SGST

43,65,114.27

1,74,207.43

0.00

41,90,906.84

4,19,090.68

37,718.16



Estimate Cost Calculation SI M/s Mehta & A

Service Connection Estimate

CONSUMER

: NO

WBS Element Work Executed by

Estimate Plan Cost

Description of Demand 43,65,114.27 Supervision Charges CGST on Supervision charges SGST on Supervision charges 419,090.68 Security Deposit Material Cost 37,718.16 Malerial Cost Storage and Handling 37,718.16 CGST on Material Cost S&H 134,000 SGST on Material Cost S&H 203,699.25 Material Cost Contengencies 6,110.98 CGST on Material Contg Charges 549.99 SGST on Malerial Contg Charges 549.99 DTR Cost 6,1_{10.98} DTR SnH Charges 549.99 CGST on DTR S&H Charges 549.99 SGST on DTR SnH Charges 1,926,600.88 DTR Conlengencies Charges 57,798.03 CGST on DTR Conlg Charges 5,201.82 SGST on DTR Contg Charges 5,201.82 Rounded-off cost 57,798.03 Total Cost 5,201.82 Note: Material cost is calculated based on Plan cost and Moving average cost - whichever



- marriagement

M/s Mehta & Modi Realty at Sy.No:- 196, Kowkoor Village ICSC Reg.No. LTM222240064 Dt:- 05.07.2022

Extension of supply to 119Nos.3-Ph each 5KW Domestic loads,1No. 3-Ph 15KW Domestic Load (Common Purpose and 1No. 3-Ph each 15KW Non-Domestic load (Club House Purpose) over and above the existing,1No.3-Ph 27KW Category-VIII load (SC.No.TS23 00005) making a total load of 652KW to M/s.Mehta & Modi Realty at Sy.No.196, Kowkoor Village in Yapral Section of Sainikpuri Sub-Division in Sainikpuri Division of Habsiguda circle under Capital Works.

REPORT ACCOMPANY THE ESTIMATE

- 1) GENERAL:- Extension of supply to 119Nos.3-Ph each 5KW Domestic loads,1No. 3-Ph 15KW Domestic Load (Common Purpose) and 1No. 3-Ph each 15KW Non-Domestic load (Club House Purpose) over and above the existi 1No.3-Ph 27KW LT Category-VIII load (SC.No.TS23 00005) making a total load of 652KW to M/s.Mehta & Modi Reat Sy.No.196, Kowkoor Village in Yapral Section of Sainikpuri Sub-Division in Sainikpuri Division of Habsiguda circle under Capital Works.
- 2) Point of Supply:- The proposed 2*315KVA Transformer will be connected to 11KV Barshipet feeder emanating from 33/11KV Kowkoorl S.S.
- 3) MAIN FEATURES :The Proposal envisages the following:
- a) Erection of 2Nos.315KVA DTR with necessary switchgear.
- b) Erection of 2Nos.S.P.Structure with Box Pole to 11KV Barshipet feeder.
- c) Stringing of 11KV line with 55Sq.mm AAA Conductor for a distance of 0.25KM over 5Nos 9.1Mtrs PSCC poles and 2Nos. Stud poles.
- d) Laying of LT 3-1/2 Core 95Sqmm UG Cable for a distance of 170 Mtrs with supporting kits.
- d) Erection of control panel-6Nos.
- e) Laying of LT 3-1/2 Core 70Sqmm UG Cable for a distance of 60 Mtrs with supporting kits
- f) Erection of 2Nos.CT Operated energy Meters (1*15KW+1*15KW)
- g) Release of 119 Nos.3-Ph Energy meters in a 6Nos Panel Boards. (119*5=119Nos).
- h) Laying of DR 11kV 3x185Sqmm UG Cable for a distance of 35 Mtrs.
- 4) POWER TRANSFORMER CAPACITY: The existing power transformer 2 Nos 5 MVA capacity at 33/11KV Kowkoor S.S. Sub-Station total MVA is 16MVA With 2Nos.8MVA Power transformers.
- 5) CAPITAL COST OF THE ESTIMATE: The capital cost of the estimate is as per the detailed estimate enclosed.
- 6) H.T REGULATION: The regulation of 11 KV Barshipet feeder has been calculated and quite found to be within permissible limits. The 11 KV Route Map along with 11 KV Regulation Chart is herewith enclosed.

Certificates:-

- 1) No UDC/OSL Services existing at Sy.No:- 196, Kowkoor Village.
- There are no Court Cases/Theft/Malpractice Cases Pending at Sy.No.196, Kowkoor Village.
- There are no AGL Services existing and no C.C.Bill dues are pending at Sy.No.196, Kowkoor Village.
- 4) The existing temporary service(TS23 00005) will be dismantled after release of service.



Estimate Number: E-2022-14-03-11-03-028

Technical Feasibility Report for Electricity supply to M/s Mehta & Modi Realty at Sy.No.196, Kowkoor Village for Extension of supply to 119Nos 3-Ph each 5KW Domestic load (119*5=595KW), 1No. 3-Ph 15KW Domestic Load and 1No.3-Ph each 15KW Non-Domestic load over and above the existing 1No. 3-Ph 27KW LT Category-VIII load (SC.No.TS23 00005) and thus making a total load of 625KW in Yapral Section of Sainikpuri Sub-division in Sainikpuri Division of Habsiguda Circle.

- Power Transformer Details/DTR Details
 - 1. Name of the sub station/DTR33/11kV Kowkoor
 - 2. Power Transformer Capacity/DTR 2X5MVA
 - 3. Voltage Ratio 33/11kV
 - 4. Proposed load 0.625MVA
- 5.Addl loads already Proposed 0.315MVA

6.whether the transformer capacity is adequate to cater the proposed loads in addition to the existing loads YES

- FEEDER DETAILS
 - 1.Name of the feeder 11KV Barshipet

2.Maximum load reached on the feeder 120A

3.Whether the regulation is within the permissible limit to cater the proposed and the existing load

- PROPOSED FEATURES FOR THE LOAD
 - 1.Length of 33/11/LT Line by tapping to the existing line 250Mtrs(OH)+70Mtrs(UG)
 - 2.Proposed DTR if any 2*315KVA
 - 3.Length of line for dedicated 33/11KV line if any 6.85KM
- COST OF THE ESTIMATE
 - 1.Approximate cost of the line,DTR,Metering and etc
 - 2.Development charges 7,50,000
 - 3. Security Deposit 1,34,000
 - 4.Total approximate cost of the Estimate(1+2+3) As Per Estimate
- DATE OF INSPECTION 12-07-2022
- VI INSPECTING OFFICER AE/OP/YAPRAL
- VII Whether feasible to issue the load
- VIII Remarks if any Multistoryed Building

YES

As Per

Estimate

| Division | : SE/O/RR East | Section | : AE YAPRAL |
|----------------|-------------------------------|--------------------------------------|------------------------------|
| Project Type | : SC-Extension of Supply (LT) | Cost Center | : 114311301 |
| Estimate No. | : E-2022-14-03-11-03-028 | Estimate Description Sy.No:- 196, | : M/s Mehta & Modi Realty at |
| Network No. | : 520000395836 | Estimate Created Date | : 16.07.2022 |
| Reservation No | . : 8002214787 | Plant | : 1060 |
| User Status | : CGMZ NBGD PAPR | System Status : CR | TD AVAC |
| Estimate Appro | ved date : | Estimate Sanctioned E | By : |

Work to be executed by : CONSUMER

| CSC Ren no. | Appl. Name | LT | Cat. | Sub.' Cat.1 | C.L1 | Cat. | Sub_ cat.2 | C.L2 | Doc.Ser. Rec.Con. | Exst. Load |
|-------------|-----------------------------------|----|------|----------------|--------|------|---------------|-------|----------------------|------------|
| | M/S MEHTA & MODI REALTY KOWKUR | LT | 01 | 000 | 610.00 | 02 | 00 | 15.00 | X | 0.00 |

| | Estimate Cost (Gross): | 4319169.82 |
|--|------------------------|------------|
| | Less Credits : | 24.92 |
| the state of the s | Estimate Cost (Net) : | 4319144.90 |



Estimate Number: E-2022-14-03-11-03-028

| | 10% Incidental Charges to be collected : | 414496.238 |
|--------|--|--------------|
| SL.No. | Proposals involves | Total in Rs. |
| 1 | 10 - Materials List | 4319169.8226 |

| S.No | Materials Code | Materials Text | Item Catagory | Quantity | Unit | Rate in Rs. | Amount in Rs. |
|------|-------------------|------------------|------------------|----------|------|-------------|---------------|
| 1 | SCR00038 | Meter body Scrap | Stock item | 0.500 | KG | 49.83 | 24.9 |



Estimate Number: E-2022-14-03-11-03-028

| | | | | Catagory | | Code | |
|-----------|-----------|------|---------|----------|---|----------|-----|
| 3,555.8 | 1,777.94 | EA | 2 | - | Erection of 11kv TT type AB switch | SWR20102 | 1 |
| 4,200.0 | 2,100.00 | EA | 2 | - | Erect- 3Ph DTR 315KVA | SWR11725 | 2 |
| 50,916.8 | 25,458.40 | EA | 2 | - | Column type DTR Plinth topslab 4'x4'x6" | SWR21843 | 3 |
| 3,380.0 | 845.00 | EA | 4 | - | Painting of RS Joist(1C RO, 2C Al.Paint) | SWR10640 | 4 |
| 2,010.0 | 502.50 | EA | 4 | - | Fabrication of 175x85/150x75mm RS joist | SWR10642 | 5 |
| 22,059.0 | 6,450.00 | М3 | 3.420 | - | Mass concreting of supports incl. cement | SWR10356 | 6 |
| 825.0 | 412.50 | EA | 2 | - | Running of 11kv jumpering to AB switch | SWR10407 | 7 |
| 1,452.0 | 726.00 | SET | 2 | - | Erect. of 11kv HG Fuseset incl earthing | SWR10395 | 8 |
| 14,520.0 | 1,210.00 | EA | 12 | - | ERECT. OF LINES-Providing of earthing | SWR10357 | . 9 |
| 7,649.7 | 3,824.87 | EA | 2 | - | Erect-12Meter Box pole | SWR11267 | 10 |
| 4,125.0 | 13.75 | М | 300.000 | - | Run-GI Earth Flat 25x3mm from metallic p | SWR12125 | 11 |
| 6,600.0 | 110.00 | М | 60.000 | - | Laying of UG Cable LT 3 1/2 x 70 Sqmm | SWR11014 | 12 |
| 26,690.0 | 157.00 | М | 170.000 | - | Laying of UG Cable LT 3 1/2 x 95 Sqmm | SWR11013 | 13 |
| 5,400.0 | 900.00 | EA | 6 | - | Erection of CT meter on LV side of DTRs | SWR10336 | 14 |
| 1,200.0 | 300.00 | EA | 4 | - | Fix-GPRS Modem & Sim Card | SWR23098 | 15 |
| 2,737.5 | 91.25 | KG | 30.000 | - | S-MS Bolts & Nuts, Washers etc., | SMR11487 | 16 |
| 11,737.0 | 97.00 | EA | 121 | -, | Release of 3Ph service | SWR10489 | 17 |
| 220.0 | 110.00 | EA | 2 | - | Paint-Structure/DTR Code & Locaiton Name | SWR11722 | 18 |
| 416,500.0 | 3,500.00 | EA | 119 | - | S&E-3Ph MtringPanel 14g with accessories | SMR23101 | |
| 2,362.9 | 9,451.68 | KM | 0.250 | - | Stringing of 55sqmm 33/11kv Line 3 Cond | SWR10365 | 20 |
| 10,800.0 | 1,800.00 | EA | 6 | - | Erect-Control Panel | SWR24835 | 21 |
| 3,933.0 | 437.00 | EA . | 9 | - | EXCAVATION OF PIT 0.6 M x 0.9 M x 1.5 M | SWR10106 | 22 |
| 13,800.0 | 2,300.00 | . LS | 6 | - | Construct-Platform for meter panel board | SWR11272 | 23 |
| 198.0 | 99.00 | EA | 2 | - | Testing of CT meter | SWR11067 | 24 |
| 800.0 | 20.00 | М | 40.000 | - | Laying of 1Core XLPE 120Sqmm Cable | SWR22356 | 25 |
| 9,296.6 | 2,324.15 | EA | 4 | - | OD/Idoor end termination 11kv 3x185 xlpe | SWR10390 | 26 |
| 21,654.1 | 618.69 | М | 35.000 | = | Lay-DR 11KV 3x185sqmm UG Cb HG/BC/CC/BT | SWR11974 | 27 |

Page 5 of 6 .



Estimate Number: E-2022-14-03-11-03-028

| 28 | SWR12006 | Raise-DR 11KV 3x185sqmm | | | | | 2 |
|------|---|--|------------|--------|-------|--------------|------------|
| _ | | UG Cb on support | - | 22.500 | М | 238.75 | 5,371.8 |
| 29 | SWR10343 | ERECTION OF LINES-Erection of 9.1M Pole | - | 5 | EA | 2,108.00 | 10,540.0 |
| 30 | SWR11083 | Erec of 9.1 Mts PSCC poles for stuts | - | 2 | EA | 2,108.00 | |
| 31 | SMR24835 | S-Control Panel-Busbar, MCCB incl.Wiring | - | 6 | EA | 18,000.00 | 4,216.00 |
| 32 | SWR10988 | Lay-2nd Cable in Excavated Trench | - | 35.000 | М | 200.10 | 7,003.50 |
| 33 | SWR10197 | LOADING of 315kva DTR | | - | | | , 7,003.30 |
| 34 | SWR10515 | UNLOADING of 315kva DTR | | 2 | EA | 601.00 | 1,202.00 |
| 35 | SWR24841 | S&Erect-LT Cntrl Pnl Board 800 | | 2 | EA EA | 534.00 | 1,068.00 |
| 36 9 | SWR24832 | & 20/GSFU | | | -/- | 43,000.00 | 172,000.00 |
| _ | | S&Erect-CT Metering Panel incl. Wiring | - | . 2 | EA | 3,500.00 | 7,000.00 |
| 37 5 | SWR20308 | SubTrnsprt 9M PSCC Pole incl. L&UL<10KM | - | 7. | EA | 399.30 | 2,795.10 |
| | | | | · · | | Service Cost | 967,819.07 |
| | | GST 18% | 174,207.43 | | | | |
| | | H Charges: | 73357.89 | | | | |
| | | on materials: | 82401.38 | | | | |
| | | ral Charges : | 274671.28 | | | | |
| | A TOP TO SERVE OF THE SERVE OF | | | | | Total: | 4319169.82 |