To,

Tata Capital. Hyderabad.

Subject: Estimate of cost of completion of building at GV1 belonging to M/s. Crescentia Labs Pvt. Ltd., situated at Plot no:15-B, Sy. No. 230 to 243, Turkapally, Shamirpet Mandal, Medchal-Malkajgiri District, Telangana

Sir/Madam,

Estimate of cost of completion at GV1.

The details considered for the estimate are as follows:

- 1. The estimate is prepared for completion RCC and Civil works of building at GV1 along with the finishing works like structural glazing, ACP, lifts, toilets, common spaces, etc. The finishing of interior spaces is to be borne by the prospective tenant.
- 2. Estimate for provision of power supply, generator backup, electrical panels, HVAC, etc., have considered for the building. Provision of these utilities and services is considered only upto high side. Provision of low side is in the scope of prospective tenant.
- 3. Cost of completing common amenities and facilities of the entire site have also been considered. Amenities like compound wall, roads, gates, ETP, STP, chemical stores, solvent stores, electrical room, underground ducting, etc., that are required for making building functional have been considered.
- 4. The total area of building is about 1,75,000 sft and the entire site is about 1.80 acres.
- 5. Note that the details of MEP services have not been finalized and are subject to minor changes based on required of prospective tenant and site conditions. Accordingly, the cost of these services may vary by +/- 10%.

Accordingly, the total cost for completion of building with required amenities and facilities is about Rs. 59 cr. The details of estimate are given in Annexure –A.

Thank You.

Yours sincerely,

Annexure -A

Estimate of construction cost for completion of building at GV1s along with required facilities and amenities.

| Sl. No. | Description of work | Estimated cost of work (in Rs. Lakhs) | Remarks | Top Vendors | Payment terms |
|------------|--|---------------------------------------|---|-------------|---------------|
| 1. | Completion of RCC & Civil structure for basement & stilt floors– 61,700 sft @ Rs. 1200/- per sft. | 74.00 | NA | | |
| 2. | Completion of RCC & Civil structure for basement & stilt floors—1,14,000 sft @ Rs. 1600/- per sft. | 1824.00 | NA | | |
| 3. | Chemical stores & Solvent stores – RCC and civil works – 11,100 sft @ Rs. 1200/- per sft. | 133.20 | NA | | |
| 4. | Civil work for sumps, storage tanks, HSD, ETP, STP, electrical power supply/back-up | 100.00 | Lumpsum cost | | |
| 5. | Underground conduiting for utilities and services | 35.00 | Lumpsum cost | | |
| 6. | Site – Driveway CC | 50.00 | Lumpsum cost | | |
| 7. | Permits | 100.00 | • | | |
| 8. | Architectural & Professional consultancies | 75.00 | Based on proposals provided by the consultants. | | |

| 9. | VDF Flooring | 150.00 | Lumpsum cost | | |
|-----|----------------------------------|--------|-----------------------|-----------------------|--|
| 10. | Toilets – 5 lakhs for one | 20.00 | Lumpsum cost | Kohler, Jaguar, Toto, | 50% advance and 50% against proforma |
| | bank of toilets x 4 nos | | _ | American Standard | invoice before dispatching the material. |
| 11. | Cafeteria furniture & fixtures | 30.00 | Lumpsum cost | | |
| 12. | Structural glazing and ACP. | 450.00 | Based on quotation | AKB Glass Systems, | 25% advance, 55% on material delivery, and |
| | | | provided by vendor. | Anvika, Sun Glazing, | balance on pro rata basis based on |
| | | | | Vibrant Facades | completion of work. |
| 13. | Structural support for | 100.00 | Lumpsum cost | AKB Glass Systems, | 50% advance and 50% against delivery of |
| | glazing & ACP. | | | Anvika, Sun Glazing, | material. |
| | | | | Vibrant Facades | |
| 14. | Power supply including HT | 700.00 | Partially based on | Dharia Switchgear, | 30% advance and 70% against proforma |
| | cable, HT panels, | | quotation provided by | Technocrafts, Sanjay | invoice before dispatching the material. |
| | transformer, LT panels, LT | | vendor and balance on | Technical, MNR | |
| | cables including installation | | lumpsum basis. | Electricals, Elecon. | |
| | and commissioning | | | | |
| 15. | Generator back-up – 2 nos. x | 250.00 | Based on quotation | JAKSON, Powerica, | 10% advance, 20% within six weeks of |
| | 1500 KVA including | | provided by vendor. | GMMCO, Greaves, | purchase order and 70% against proforma |
| | installation, cables, panel, etc | | | Perkins. | invoice before dispatching the DG set. |
| 16. | Earthing | 10.00 | | | |
| 17. | Lifts | 150.00 | Lumpsum cost | Johnson, OTIS, | 15% advance, 60% on submission on GA |
| | | | | Schindler, | drawings, 15% against material delivery, |
| | | | | Thyssen Krupp. | 10% after testing and before handing over of |
| | | | | | the lift, |
| 18. | Chillers – 2 nos – 400TR | 250.00 | Based on quotation | TRANE, Carrier, | 100% Letter of credit, or 50% advance and |
| | | | provided by vendor. | YORK, | 50% against proforma invoice before |
| | | | | Blue Star. | dispatching the material. |
| 19. | HVAC – Common areas | 50.00 | Lumpsum cost | Blue Star, Carrier, | 50% advance, balance 50% before dispatch |
| | | | | Daikin | |
| 20. | Insulated piping for chillers | 150.00 | Partly based on | Pumps – Grundfos, | 50% advance, balance 50% before dispatch |
| | with control valves, pumps, | | quotation provided by | KSB, Armstrong. | |
| | etc. | | vendor and balance on | | |
| | | | lumpsum basis. | | |

| 21. | Fire safety equipment like down comers, yard hydrant, booster pumps, jockey pump, diesel pump, fire extinguishers, etc | 75.00 | Lumpsum cost | Valves – Audco, Zoloto, Newage, NVR. | |
|-----|--|-------|--|---|---|
| 22. | Fire hydrant, yard hydrant installation | 30.00 | Lumpsum cost | | |
| 23. | Fire doors | 15.00 | Based on quotation provided by vendor | Ahlada, Shakti Hormann, Aacess, iClean. | 50% advance and 50% against proforma invoice before dispatching the material. |
| 24. | STP – 30KLD | 15.00 | Based on quotation provided by vendor. | Watervision, Thermax, Revolve, Better Enviro care, Ultra Water, Enviro Axis. | 20% advance, 30% on material ready advice, 30% on delivery of material, 10% on installation and 10% on commissioning. |
| 25. | ETP – 45KLD | 20.00 | Based on quotation provided by vendor. | Watervision, Thermax, Revolve, Better Enviro care, Ultra Water, Enviro Axis. | 20% advance, 30% on material ready advice, 30% on delivery of material, 10% on installation and 10% on commissioning. |
| 26. | Water Softener – 50 KLD | 2.00 | Based on quotation provided by vendor. | Watervision, Thermax, Revolve, Better Enviro care. | 50% advance, 50% on installation & commissioning. |
| 27. | HSD – 15 KL, PESO License | 40.00 | Based on quotation provided by vendor. | RK Petro, SGIC. | 20% advance, 30% against material delivery, 40% on installation, 10% on commissioning. |
| 28. | Air Compressor | 12.00 | Based on quotation provided by vendor. | Ingersoll | 50% advance, balance 50% before dispatch. |
| 29. | Centralised Vacuum | 12.00 | Based on quotation provided by vendor. | Toshniwal | 50% advance, balance 50% before dispatch. |

| 30. | Piping for compressed air & | 15.00 | Based on quotation | MMN Lab, Tapco |
|-----|-----------------------------|---------|---------------------|----------------|
| | vacuum | | provided by vendor. | |
| 31. | Security cameras and | 5.00 | Lumpsum cost | |
| | equipment | | | |
| 32. | Lighting and landscaping | 30.00 | Lumpsum cost | |
| 33. | Miscellaneous MS | 100.00 | Lumpsum cost | |
| | fabrication works | | | |
| 34. | Miscellaneous – plumbing, | 50.00 | Lumpsum cost | |
| | electrical, miscellaneous | | | |
| 35. | Administration and utility | 270.00 | Lumpsum cost | |
| | cost – 15 lakhs @ 18 months | | | |
| 36. | Finance cost | 200.00 | NA | |
| 37. | Miscellaneous and | 250.00 | NA | |
| | unforeseen expenses | | | |
| | Total cost: | 5,842.2 | | |