

QUOTATION - 003.1/ANV/GV1 (Dated 5.4.24)								
Sub: GV1 Structural Glazing & ACP Company: Crescentia Labs Pvt. Ltd. PROJECT : GV-1 WEST ELEVATION							 ANVIKA FACADES	
BOQ PROPOSAL FOR GV-1 ELEVATION GLAZING & CLADDING WORKS. ALL QTY BY CLIENT (Except EAST ELEV & TERRACE PERGOLA & NORTH								
S.NO.	ITEM DESCRIPTION	Elevation	LOCATION	TYPE	AREA	UOM	UNIT/ RATE	AMOUNT
1A	Acp Cladding NON FR Vertical Fin 1250 x 300	External	Western	U Shape All Elevations	1500	SQM	4005.00	6,007,500
1B	Acp Cladding Main Entry Inclined Canopy	Portico	Western	Inclined Shape		SQM	4773.00	
1C.1	Curtainwall FIXED Glazing with 24mm DGU (6SKN+12AG+6CLR)	External	Western	Gr Floor		SQM	9118.00	-
1C.2	Curtainwall FIXED Glazing with 6MM SGU Glazing With No RED Film / No RED Cap	External	Western	Atrium Lobby	210	SQM	7700.00	1,617,000
1D	Vertical Louvers 100x50	External	Western	300mm Centre to Centre	2800	RMT	1260.00	3,528,000
1E.1	Fixed Casement Window with 24mm DGU (6SKN+12AG+6CLR)	1.5x2.35 Clear Opening	Western	Elevation Grid 1-4 & 5-8	135	SQM	8370.00	1,129,950
1E.2	2 Track Sliding Window 27mm Series with 21mm DGU (6SKN+10AG+5CLR)	1.5x2.35 Clear Opening	Western	Except Staircase	60	SQM	8750.00	525,000
1F	MS Acp Frame work For Vertical Fins & Canopy (LOBBY CRIS CROSS MS Frame bt Client Directly)					KGS	55.00	-
							BASIC COST	12,807,450
							GST	2,305,341
							TOTAL	15,112,791
General Terms :-								
Basic Cost considered, GST Extra								
GI Flashing shall be Rs. 1485/-/Rmt Extra , Smoke seal & Firestop shall be Rs. 2750/-/Rmt Extra, Spandrel Insulation shall be Rs. 2975/-/Sqm Extra & Openable @ Rs. 9350/-/No.								
Free Power supply & Storage area to be provided to us								
Final payment shall be subject to actual work done at site								
Optimized Glass size is considered.								
Scaffolding to be provided to us for all our works								
Quote validity for 1 week from today (10th April, 2024), any price escalation will be extra								
Payment Terms :-								
Advance 40% along with Work order								
10% upon Aluminium Frame work								
30% upon GLASS / ACP Delivery								
10% upon GLASS / ACP Installation								
10% upon Final completion & handing over								