

To  
M/s. Modi Properties Pvt. Ltd  
Hyderabad  
Contact: 95022 77299  
Email Id: prabhakar@modiproperties.com

Date : 20.08.2024  
Ref :- AKBG/2024-225/032 R2

Kind Attn: Mr. Prabhakar

Sub: Quotation for Vertical Rafter works for your Proposed Project of DP-24 Diamond Point

Dear Sir,

We thank you for your above enquiry & are pleased quote our best rates for fixing of the above requirement with specifications as under

Sl.No	Description	Unit	Approx Qty	Rate	Total
1	<b>Aluminium Vertical Rafter's @ 100 mm IN/IN</b>				
	Providing, fabricating and fixing in position of Powder coated aluminium vertical rafters of approved make using 100X50X2mm Box section for rafters, 75X75X3mm L-Angle for horizontal Support and Bracket made out of Aluminium extruded powder coated sections, Specially designed to withstand wind pressure at 1.2 Kpa. Fixed at all levels, elevations and heights to the masonry / RCC walls with necessary clamps, brackets and GI anchor fasteners of WRUTH/KLIMAS MAKE. Other fastening straps, nuts, bolts,washers,etc.	RMT	215	1,100.00	2,36,500.00
2	<b>MS SUPPORT FRAME WORK</b>				
	Supply & fixing of MS Support Frame work made of Box Section of 100 x 100mm, with one coat of Red oxide. <b>As and where if required</b>	Kgs	200	175.00	35,000.00
<b>Approx Total Work Value Excluding Taxes</b>					<b>2,71,500.00</b>
<b>GST @</b>				<b>18%</b>	<b>48,870.00</b>
<b>Approx Total Work Value Including Taxes</b>					<b>3,20,370.00</b>

- Note:**
- The above quantities are approximate only, however the final bill will be made as per the actual site measurements.
  - Any further taxes levied on this work by the government with the amendment in the act effective, retrospectively will be charged extra.
  - Rates have been determined based on the received drawings. Please note that any deviations from these drawings may result in a revision of the quoted rates.

**Note:** Due to the unprecedented market dynamics, this year has seen extraordinary pressures on the prices of our raw material & other input costs. Such as Aluminium, Glass, Silicon, Aluminium Composite Panel and Hardware Etc. The offer price shall be finalized on the day of confirmation of order and advance payment.

#### **PAYMENT TERMS**

Payment: 50% Advance along with the work order.  
40% on the receipt of material at the site.  
10% on completion of the work.

1. We have quoted as per information received and in reply to the specification only, any modification will require corresponding revision of rates.
2. Tolerance and forms for flat Toughend glass.
  - a. Deviation of form +/- 3mm
  - b. Straightness of edge < 3mm /m
  - c. Twisting < 4mm / m
3. All the final glass measurements/sizes will be taken + 50mm (In both Widht & Height) as standard to the actual glass measurements/sizes.
4. Deliveries will be made against Delivery Challans which the client/client's representative has to acknowledge.
5. The liability for safe keeping of material delivered at site lies with the client's scope.
6. Lockable room to be provided by client at site for safe storage of material, tools & workmen.
7. Electrical connection to be provided by client wherever necessary at site.
8. Any civil defects to be rectified by your person at your cost.
- 9. Scaffolding to be provided by client wherever necessary at site.**
10. Sealing the gaps between the masonry structure and aluminium frames do not fall under our scope of work.
11. MS Frame if necessary to be provided by you or by us at an extra cost.
12. You should ensure necessary plumb levelled flooring & roofing.
13. Quotation validity 15 Days.

We at **AKB Glass Systems** are committed to customer care and shall always be available to attend to any kind of assistance requested.

Thanking you and assuring you of our best services at all times.

**Yours faithfully,  
For AKB Glass Systems**



**Dinkar Bhardwaj  
M: 9849066044**