

Tax Invoice

(ORIGINAL FOR RECIPIENT)

e-Invoice



IRN : 37fdf1e47e419142d2c7ed78304fbef80691bfa595d12-503bd01359469769fbb
Ack No. : 112523561674296
Ack Date : 28-Jan-25

 VVE TRANSFORMERS Kumbury Street, Visakhapatnam	VVE Transformers Private Limited-24-25 Plot No.62/2, C.I.E, Gandhinagar, Balanagar Extn, Hyderabad-500037 UDYAM : UDYAM-TS-20-0009660 (Small/Mfgr) GSTIN/UID : 36AAECV7146H1Z3 State Name : Telangana, Code : 36 E-Mail : vvetransformers@gmail.com	Invoice No. VVETPL/191 e-Way Bill No. 112033295262 Dated 28-Jan-25																													
	Delivery Note	Mode/Terms of Payment																													
Reference No. & Date.		Other References																													
Buyer's Order No. 20241028032		Dated 28-Oct-24																													
Dispatch Doc No. VVETPL/191		Delivery Note Date																													
Dispatched through		Destination																													
Bill of Lading/LR-RR No.		Motor Vehicle No. TG31T0869																													
Terms of Delivery																															
<table border="1"><thead><tr><th>SI No.</th><th>Description of Goods</th><th>HSN/SAC</th><th>Quantity</th><th>Rate</th><th>per</th><th>Amount</th></tr></thead><tbody><tr><td>1</td><td>1000KVA-DTR-OLTC 11KV/433V, 3-Phase, 50Hz, Oil Cooled, Out Door Type, Copper Wound, +10% To -10% Instep of 1.25% 17-Position Taps OLTC with AVR, Both Side Cable Box Conventional Distribution Transformer As Per IS 1180/2014 EEL-2 RTCC Panel Included 01 No.</td><td>85043300</td><td>1 NOS</td><td>23,75,000.00</td><td>NOS</td><td>23,75,000.00</td></tr><tr><td colspan="6"></td><td>4,27,500.00</td></tr><tr><td colspan="6">Total</td><td>1 NOS</td><td>28,02,500.00</td></tr></tbody></table>			SI No.	Description of Goods	HSN/SAC	Quantity	Rate	per	Amount	1	1000KVA-DTR-OLTC 11KV/433V, 3-Phase, 50Hz, Oil Cooled, Out Door Type, Copper Wound, +10% To -10% Instep of 1.25% 17-Position Taps OLTC with AVR, Both Side Cable Box Conventional Distribution Transformer As Per IS 1180/2014 EEL-2 RTCC Panel Included 01 No.	85043300	1 NOS	23,75,000.00	NOS	23,75,000.00							4,27,500.00	Total						1 NOS	28,02,500.00
SI No.	Description of Goods	HSN/SAC	Quantity	Rate	per	Amount																									
1	1000KVA-DTR-OLTC 11KV/433V, 3-Phase, 50Hz, Oil Cooled, Out Door Type, Copper Wound, +10% To -10% Instep of 1.25% 17-Position Taps OLTC with AVR, Both Side Cable Box Conventional Distribution Transformer As Per IS 1180/2014 EEL-2 RTCC Panel Included 01 No.	85043300	1 NOS	23,75,000.00	NOS	23,75,000.00																									
						4,27,500.00																									
Total						1 NOS	28,02,500.00																								
Amount Chargeable (in words) : INR Twenty Eight Lakh Two Thousand Five Hundred Only INR Twenty Eight Lakh Two Thousand Five Hundred Only																															
<table border="1"><thead><tr><th>Taxable Value</th><th>IGST Rate</th><th>IGST Amount</th><th>Total Tax Amount</th></tr></thead><tbody><tr><td>23,75,000.00</td><td>18%</td><td>4,27,500.00</td><td>4,27,500.00</td></tr><tr><td>Total: 23,75,000.00</td><td></td><td>4,27,500.00</td><td>4,27,500.00</td></tr></tbody></table>			Taxable Value	IGST Rate	IGST Amount	Total Tax Amount	23,75,000.00	18%	4,27,500.00	4,27,500.00	Total: 23,75,000.00		4,27,500.00	4,27,500.00																	
Taxable Value	IGST Rate	IGST Amount	Total Tax Amount																												
23,75,000.00	18%	4,27,500.00	4,27,500.00																												
Total: 23,75,000.00		4,27,500.00	4,27,500.00																												
Tax Amount (in words) : INR Four Lakh Twenty Seven Thousand Five Hundred Only																															
Company's Bank Details A/c Holder's Name : VVE Transformers Private Limited Bank Name : Canara Bank OD A/c.No.5332 A/c No. : 0625256005332 Branch & IFS Code : Balanagar & CNRB0000625																															
Company's PAN : AAECV7146H	Customer's Seal and Signature																														
for VVE Transformers Private Limited-24-25		Authorised Signatory																													

SUBJECT TO HYDERABAD JURISDICTION

This is a Computer Generated Invoice

"TRUE COPY"

**WAY BILL Details**

Way Bill No: 1120 3329 5262

Generated Date: 28/01/2025 04:29 PM

Generated By: 36AAE CV714 6H1Z3

Valid Upto: 01/02/2025

Mode: Road

Approx Distance: 673km

Type: Outward - Supply

Document Details: Tax Invoice - VVETPL/191 - Transaction type: Regular
28/01/2025

IRN: 37fdf1e47e419142d2c7ed78304fbef80691bfa595d12503bd01359469769fbb

2. Address Details**From**

GSTIN: 36AAE CV714 6H1Z3

VVE Transformers Private Limited-24-25

TELANGANA

:: Dispatch From ::

Plot No.62/2,C.I.E, Gandhinagar,, Balanagar Extn, Hyderabad-500037

Telangana,TELANGANA-500037

To

GSTIN: 37AAX CA563 8G1Z4

Amtz Medpolis Square 801 Private Limited

ANDHRA PRADESH

:: Ship To ::

D1-95 & E2-109, Ground, Amtz Medpolis Square 801, Pragati Marg,

Visakhapatnam, Vm Steel Projct Town

Ship Sub Post Office, Visakhapatnam

Andhra Pradesh ANDHRA PRADESH-530031

3. Goods Details

Please Refer IRN Print to view Goods Details.

Tot. Tax'ble Amt	CGST Amt	SGST Amt	IGST Amt	CESS Amt	CESS Non.Advol Amt	Other Amt	Total Inv.Amt
2375000.00	0.00	0.00	427500.00	0.00	0.00	0.00	2802500.00

4. Transportation Details

Transporter ID & Name :

Transporter Doc. No & Date :

5. Vehicle Details

Mode	Vehicle / Trans Doc No & Dt.	From	Entered Date	Entered By	CEWB No. (If any)	Multi Veh.Info (If any)
Road	TG31T0869	Telangana	28/01/2025 04:29 PM	36AAECV7146H1Z3	-	-



112033295262

Note*: If any discrepancy in information please try after sometime.

VVE TRANSFORMERS PRIVATE LIMITED

MANUFACTURING OF POWER & DISTRIBUTION TRANSFORMERS

IS-1180
CERTIFIED



TRANSFORMER TEST CERTIFICATE

(MANUFACTURED TO SPECIFICATION REF NO. IS:1180/2014 PART-1 BIS STANDARD)

Transformer S.No. V - 587 BIS Licence No: 6300090908 Date: 28.01.2025

OLTC,CTR SI NO.24TC1P2282 DATE: 19.12.2024.

Customer: M/s.AMTZ 801 PRIVATE LIMITED,VM STEEL PROJRT TOWN SHIP POST OFFICE,GROUND,PLOT NO.D1-56,HUB BUILDING,AMTZ CAMPUS,PRAGATIMAIIDAN,VISHAKHAPATNAM,ANDHRA PRADESH.

KVA 1000 (Cu) Phase 3 Cycles 50 c/s Type ON/AN
TYPE :Coventional OLTC 17 position,(LV Busduct & HV Cable box Outdoor Type) ENERGY EFFICIENCY LEVEL-2
H.V.Voltage 11000 Volts and Current 52.49 Amps.
L.V.Voltage 433 Volts Full Load Current 1333.41 Amps.

Tapping on H.V.Winding Yes

Connections : Delta / Star

Vector Group Ref: Dyn 11.

Test Results	Measured	Guaranteed as per BIS
% Mag. Current & Amp.s	0.24% 3.149	Amps at rated volts and 50 c/s 3.00 %
No Load Losses	1005.20	Watts at rated volts and 50 c/s
Load Losses at 50%	1490.62	Watts at rated Ampss & 50 deg.C
Load Losses at 100%	5962.46	Watts at rated Ampss & 75 deg.C
Max.Losses at 50% Load	2495.82	Watts at rated Ampss & 75 deg.C 2620 Watts
Max.Losses at 100% Load	6967.66	Watts at rated Ampss & 75 deg.C 7000 Watts
Impedance %	5.10 561	Volts at rated Ampss & 75 deg.C 5.00% (+/- 10% Tol.)

Resiatance/Phase at 20 deg.C H.V. 0.810 Ohms L.V. 0.00031 Ohms

Separate-Source Voltage Test on HV Winding 28 KV withstood for 1 minute at 31 deg.C
on LV Winding 3 KV withstood for 1 minute at 31 deg.C

Induced Over Voltage Test:2 X Rated voltage withstood for 1 minute at 100 c/s and at 31 deg.C

Insulation Resistance value :

LV winding to Earth 500 DC Volts for 60 Secinds 2000 Mega Ohms at 31 deg.C
HV winding to Earth 5000 DC Volts for 60 Secinds 2000 Mega Ohms at 31 deg.C
HV winding to LV 5000 DC Volts for 60 Secinds 2000 Mega Ohms at 31 deg.C

Tap Position	1	2	3	4	5	6	7	8	9
Turn Ratio U - Phase	48.40	47.85	47.30	46.75	46.20	45.65	45.10	44.55	44.00
	10	11	12	13	14	15	16	17	
	43.45	42.90	42.35	41.80	41.25	40.70	40.15	39.60	
V - Phase	1	2	3	4	5	6	7	8	9
	48.40	47.85	47.30	46.75	46.20	45.65	45.10	44.55	44.00
	10	11	12	13	14	15	16	17	
	43.45	42.90	42.35	41.80	41.25	40.70	40.15	39.60	
W- Phase	1	2	3	4	5	6	7	8	9
	48.40	47.85	47.30	46.75	46.20	45.65	45.10	44.55	44.00
	10	11	12	13	14	15	16	17	
	43.45	42.90	42.35	41.80	41.25	40.70	40.15	39.60	

Load as Percentage Full Load 125 100 75 50 25
Percentage Efficiency at U.P.F 97.98 98.29 98.57 98.77 98.64
Percentage Efficiency at 0.8 P.F 97.48 97.87 98.22 98.46 98.31
Percentage Regulation at F.L & UPF 0.600 and at F.L & 0.8 P.F 3.516

Pressure Test	The Transformer bolted cover was tested at pressure of 35kPa above atmosphere pressure maintained inside the tank for 10 min.			No Leakage Observed
Oil Leakage Test	Time	Result	There should be no leakage	
	8 Hours	ok	any point.	

The Dielectric strength value of oil is 60 KV (rms)Inst. As per IS-335/1983, Ratio and Polarity are found OK.

Guarantee : 12 Months from the date of dispatch

For VVE Transformers private Limited.

Testing Engineer.

HEAD OFFICE / WORKS : 62/2, C.I.E, Gandhinagar, Balanagar Extn, Hyderabad - 500 037, TS.

Office No.: +91 93475 20451, Mob.: +91 9362 191919 | Web : www.vvetransformers.com

Email : vvetransformers@gmail.com, info@vvetransformers.com.

VVE TRANSFORMERS PRIVATE LIMITED

MANUFACTURING OF POWER & DISTRIBUTION TRANSFORMERS



Date: 28.01.2025.

GUARANTEE CERTIFICATE

We are Supplying 1No. of 1000 KVA, 11000/0.433 Volts, 3-phase, 50 Hz, CRGO Core, Copper Wound, oil cooled, OLTC 17 Position, LT Busduct & HT Cable box Out door type Conventional Distribution Transformer to

M/s. AMTZ 801 PRIVATE LIMITED, VM STEEL PROJRT TOWN SHIP POST OFFICE, GROUND, PLOT NO. D1-56, HUB BUILDING, AMTZ CAMPUS, PRAGATIMAIDAN VISHAKHAPATNAM, ANDHRA PRADESH.

Transformer S. No.: V - 587

The Transformers has been Guaranteed for a period of 10-Months from date of dispatch or 12-Months from the date of Commissioning, whichever is early, against defective material and workmanship only Subject to the following Conditions.

TRANSFORMERS
Formerly Vinod Vikram Electronics

Note: If the Transformer failed due to not following of maintenance schedule, it will not Cover the guarantee.



[Signature]
VVE Transformers private Ltd.

P.T.O

HEAD OFFICE / WORKS : 62/2, C.I.E, Gandhinagar, Balanagar Extn, Hyderabad - 500 037, TS.
Office No.: +91 93475 20451, Mob.: +91 9362 191919 | Web : www.vvetransformers.com
Email : vvtransformers@gmail.com, info@vvtransformers.com.