

GSTIN : 37ACFS0619P1ZB



SRI VENKATESWARA
POWER SYSTEMS
 A - GRADE ELECTRICAL CONTRACTORS UPTO 33KV
 CPRI APPROVED LT PANEL BOARD MANUFACTURER

QUOTATION

Client :

M/s. Modi Properties

Site : MED POLIS, AMTZ, Visakhapatnam

Kind Attn : Mr. Apparao sir

Q. No. SVPS/Q/24-25/824-R1

Date : 7-Apr-25

Sub : Offer for Supply & Installation of 1600A Rated Outdoor Busduct

S No	Description	Qty	UOM	Rate	Amount
1	Supply and Installaion of 1600A Rated Outdoor Busduct with canopy From 1000KVA Transformer LT Side to 1600A Kiosk I/C Flange Type of Enclosure : IP 55 - Outdoor Type Sizes : H-300mm x W-800mm x L-1 RM MOC : 2.0mm & 1.6 mm Thick CRCA Sheet Painting : Powder Coating : RAL 7032 Busbar : 1600A TPN Aluminum Busabar (Jindal EC Grade) Ph : 2R - 100 x 10mm , N : 1R - 100 x 10mm, E : 2R-50 x 10mm	3.5	RM	41,650.00	145,775.00
2	Supply and Installation of 1600A Rated Braided Copper Flexibles at Transformer End (7 Nos per End) Size Ph: - 1R - 100 x 10mm, 500mm Length - Total 3 Nos N: - 1R - 100 X 6mm, 500mm Length - Total 1 No	1	Set	31,150.00	31,150.00
3	Supply and Installation of T-Type Mechanical Support of the above busduct made of 100 x 50mm ISMC	1	Set	7,500.00	7,500.00
				TOTAL	184,425.00
				GST : 18%	33,196.50
				G TOTAL	217,621.50

Terms & Conditions:

Payment Terms for Supply : 40% Advance along with PO, Balance 60% With taxes before dispatch against Proforma invoice.

Delivery : 2-3 Weeks from the date PO

Validity : 30 days.

Taxes : GST 18% Extra on actuals.

P&F : Inclusive

Transportation : FOR your site

Unloading & Installation : N/A

Commissioning : Inclusive

For **SRI VENKATESWARA POWER SYSTEMS**

P GOPI KRISHNA

9908043093

OFFICE & WORKSHOP : Plot No. 20, G-Block, IDA, Autonagar, Opp. BDL, Visakhapatnam-530046

Ph : 9908043093, 9052646496 | E-mail : srivenkateswaraee73@gmail.com | Web : www.svpsvizag.com