AIRTECH COOLING SERVICES DAKIN Authorised Dealer SHOP NO. 43, KHAN LATEEF KHAN ESTATE, ABIDS, HYD-500001 Contact-7799614877, 040-42010096 VRV_BOQ_AMTZ_801 02/05/2025 Proejct Location HYD Sub VRV-X BOD S.No Location **Designed TR Selected TR** Qty Total TR MODEL Area Type of unit FLOOR AREA RM/PM STORE 925 7.71 2.66 4 10.64 4 Way Cassette WH ROOM 109 2 0.90 1.65 4 Way Cassette 1 1.65 3 DOCUMENT STORE 172 1.44 2.08 1 2.08 4 Way Cassette OFFICE 4 377 3.14 2.08 2 4.16 4 Way Cassette 5 FGS 283 2.36 1.65 2 3.30 4 Way Cassette TOTAL 10 21.83

Circuit	IDU TR	IDU HP	ODU HP	DIV%
Circuit-1	21.83	26.30	20	132%

AIRTECH COOLING SERVICES SHOP NO. 43, KHAN LATEEF KHAN ESTATE, ABIDS, HYD-500001 Contact-7799614877, 040-42010096



Authorised Dealer

				Autilo	i iscu Dealei	
	ANNEXURE - I					
	B.O.Q FOR HIGH SIDE EQUIPMENT					
.No	Description	Unit	QTY	Price	Total Amount	
1	Supply of Variable Refrigerent Volume Outdoor units with inverter technology scroll compressor, low noise propellor type aero spiral fan, Condenser coil with special acrylic pretreatment for improved resistance to salt corrosion,refrigerant shut off valves,safety devices, lead free PC boards suitable for operation on R410a.					
1.1	20.0 HP (Model No :- RXQ20ARY6) Top-Discharge.	Nos	1	2,99,156	2,99,156	
1.2	DGT joint	Nos	2	2,500	5,000	
2	Supply of Variable Refrigerent Volume Indoor units with wireless remote.4 Way Cassette Type Units.					
2.1	1.65 TR - Model No : FXFSQ50ARVE6.	Nos	3	36,400	1,09,200	
2.1	2.08 TR - Model No : FXFSQ63ARVE6.	Nos	3	37,232	1,11,696	
2.2	2.66 TR - Model No : FXFSQ80ARVE6.	Nos	4	41,080	1,64,320	
				TOTAL	6,89,372	
				GST@28%	1,93,024	
	TOTAL EQUI	PMENT	VALUE '	WITH TAX	8,82,396	
	ANNEXATOR					
	ANNEXURE - II					
S.No	B.O.Q FOR LOW SIDE Description	Unit	QTY	RATE	Amount	
.110	Description	Unit	QII	KATE	Amount	
1	Lifting, Shifting, Positioning & Commissioning of the Units (Out door units located Terrace level & Out Side)	Nos	1	5,000	5,000	
2	Lifting ,Shifting ,Positioning of the indoor Units, Cassettes.	Nos	10	2,500	25,000	
3	Supply & installation of copper refrigerant piping the following sizes duly insulated with nitrile insulation of 19mm thick for pipes above 1" dia and 13mm thick for pipes below 1" dia.	Rmt	75	1,500	1,12,500	
4	Supply & Installation of control cum transmission wiring to be properly laid in PVC conduit & of Copper 2 core 1.0 sqmm (cord) as per the approved routing	Rmt	150	120	18,000	
5	Pressure testing & Commissioning of total VRV system	HP	20	1,150	23,000	
6	Supply & Installation PVC drain piping, 25 & 32	Rmt	100	100	10,000	
		TOTAL	LOWSI	DE VALUE	1,93,500	
	GST @ 18% TOTAL LOW SIDE VALUE WITH GST					
	CRAND	TOTAL	OF THE	PROJECT	11,10,726	
	UKAND	IOIAL		TROJECT	11,10,720	
	Note: FINAL BILLING AS PER SITE MEASUREMENTS					
	NUIC. FINAL DILLING AS FER SHE MEASUREMENTS					

VRV - SUMMARY								
Sl.No	Item Description	Basic Amount	GST (%)	GST Amount	Grand Total			
	VRV-X							
1	For Equipment Cost	6,89,372	28%	1,93,024	8,82,396			
2	For Low Side Cost	1,93,500	18%	34,830	2,28,330			
	Grand Total	8,82,872		2,27,854	11,10,726			
Terms &	Terms & Conditions :-							
	Power Supply required at Outdoor, should be provided by the customer,							
1-	Voltage range should with in 390-440 Volts for three phase and 220-240 Volts for Indoor units.							
2-	All Electrical (DP to ODU, MCB's, ELCB, DP to Indoor) related works should							
2-	be provided by the customer.							
3-	Warranty terms in PO as 12 months from the date of commissioning or							
J-	15 months from the date of supply whichever ends earlier.							
4-	All Civil (Core Cutting, Chipping, Outdoor Stand) related works in							
	customer scope.							
5-	If Scaffolding or Iron Fabrication is required, it will be additional charges.							
6-	Final billing will be done as per the actual measurements.							
7-	Payment to be made by crossed cheque made out in the name of:							
	AIRTECH COOLING SERVICES							
Dowmon	at Summary							
	nt Summary : - escription				Amount			
For Equ		8,82,396						
For Lov	1,14,165							
For Lov		68,499						
	Low Side: Balance final payment shall be made after completion of 45,666							
Grand Total								