

Company Name:	AMTZ Medpolis Square 801 Pvt.Ltd	Approved by:	
Project:	AMTZ 801 Pvt.Ltd	Contractor	Simhaa Constructions
Work Description:	Security Kiosk - SW	Start Date	
Prepared By	QS HO	End Date	
Date:	28 May 2025		

Sl.no	Item head	Description	UOM	Quantity	Rate	Amount	Sub Total	Remarks
1	Civil Works	Brickwork_6"	Sft	319	75.00	23,925		
		Internal Plastering	Sft	486	36.00	17,496		
		Ceiling Plastering	Sft	286	36.00	10,296		
		External Plastering	Sft	548	38.00	20,824		
		Terrace Screed M20 RMC	Cum	2	4347	8,694		
		Lifting Charges	Cum	2	130.00	260		
		VDF -Terrace WP	Sft	116	113.00	13,108		
		Lintels - 6"	Rft	16	166.00	2,656		
		PCC M10 - RMC	Cum	2	3673.00	7,346		
		PCC M10 - Labour	Cum	2	565.00	1,130		
		IWC Material	Cum	12	100.00	1,200		
						Total Amount	1,06,935	
						Add GST @ 18%	19,248	
						Total incl.GST	1,26,183	

SKO

9891

