

To.  
M.D.  
**murthy@modiproperties.com**

---

**From:** "DHEERAJ ANANTHOJ" <pragatipools@gmail.com>

**Date:** 08 September 2018 12:22

**To:** <murthy@modiproperties.com>

**Attach:** SERENE FARMS VILLA POOL.pdf

**Subject:** SERENE FARMS VILLA POOL QUOTE , Villa no. 17.

Quotation enclosed. By rates negotiated with  
Mr. Dheeraj (Prayali Consultants)

T.D. Murthy  
8/9/18.



## **pragati consultants**

**SWIMMING POOLS\*CONSULTANTS\*CONTRACTORS**

**L1.Lattitude Tower, Timberlake colony, Gachibowli road, Hyderabad 500008**

**Ph : 65702402, Mobile : 9848131574, .**

**Email: pragatipools@gmail.com**

**WWW.PRAGATIPOOLS.COM**

---

**TO,**

**M/S MODI PROPERTIES & INV (P) LTD ,**

**M.G ROAD .**

**.SECUNDRABAD.**

**DATE:08-09-18.**

**SUB : Quotation for swimming pool equipments and  
Consultancy for swimming pool at SERENE FARMS, CHEVELLA**

Sir,


We are here by forwarding the Quotation for the swimming pool technical consultancy and the filter equipment for your project SERENE FARMS

Hoping the quotation is clear in all respects, and in case of any clarification please  
Kindly get back to me.

Thanking you.

For PRAGATICONCONSULTANTS

(DHEERAJ ANANTHOJ)



# pragati consultants

**SWIMMING POOLS\*CONSULTANTS\*CONTRACTORS**

L1.Lattitude Tower, Timberlake colony, Gachibowli road, Hyderabad 500008

Ph : 65702402, Mobile : 9848131574,

Email: pragatipools@gmail.com

WWW.PRAGATIPOOLS.COM

## QUOTATION FOR FILTER SYSTEM/ACCESSORIES


Swimming Pool Size : 10'X18'X4' DEEP  
Swimming pool Capacity : 4500 Gallons (21M3)  
Turnover Period : 1.5 hours (per cycle)  
PSF Capacity (Flow rate) : 1 Nos x 50 gpm( 15 m3/HR)

|   | Particulars                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Quantity          | AMOUNT                |
|---|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|-----------------------|
| 1 | <b><u>Supply of FILTER CIRCULATION SYSTEM</u></b><br>Consisting <b>IMPORTED Compact POLYESTER FRP Pressure</b> filter of Diameter <b>800mm</b> with INLET AND OUTLET for the filtered water and pool water with under collection piping hub with laterals for water out let with max working pressure upto 10 bar, with the shell made of HIGH GRADE POLYESTER +FRP(LAMINATED). With filtration rate of 40M3/HR/M2. Maxium FLOW RATE upto 30M3/HR.( MIDAS/CWG/MINDER) Including <b><u>MULTI PORT VALVE FOR FILTER./ CONNECTORS</u></b> | 1 NO<br>@85,000/- | Rs 85,000<br>80,000/- |
| 2 | <b><u>CIRCULATION PUMP./STARTER/PREFILTER.</u></b><br>Supply, of 1 NO 2 HP <b>KIRLOSKER MONOBLOC PUMP</b> SP1HM Model ( Self priming) With discharge of 15m3/hr - 20m3/hr<br><b><u>Note:</u></b> Electrical connection should be arranged by the client.                                                                                                                                                                                                                                                                               | 1 NO              | Rs 30,000<br>26,500/- |

|              |                                                                                                                                                                                                                                                                                                                                 |                             |                              |
|--------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------|------------------------------|
| 3            | <b><u>INLET NOZZLES/ SHELL FITTINGS/ DRAINS</u></b><br>With required ABS SURFLOW INLET NOZZLES, ANTI VORTEX . And other fittings and connectors.                                                                                                                                                                                | 3 Nos                       | Rs 3000 ✓                    |
| 4            | <b><u>Supply of SUCTION/ VACCUM SWEEPING HEAD.</u></b> Brush head Made of SS(316) Sheet metal 2mm th ,with PP(Replaceable brushes )with black tough plastic bristles, along with the HOSE PIPE. Including the required fittings and connectors to the PUMP. (With hose pipe) and SS handle.(6m)                                 | 1 SET                       | Rs 30,000 ✓<br>28,000/-      |
| 5            | <b><u>SS POOL LADDERS/GRAB RAILS( SS 316 pipe/ sheet).</u></b><br>With mirror finish , steps,sheet bended, ss nut bolt fastened STEPS with M.S Flat for Fastening and permanent grouting).<br>SS LADDER – 1NOS, @ 18,000/- each 16,500/-<br>GRABRAILS- 4 NOS @ 2000/- each                                                      | 20000/- 16,500<br>8000/- ✓  | Rs 20000 ✓<br>Rs 8000 ✓      |
| 5            | <b><u>Supply of Underwater light fixtures.</u></b><br>High Temperature Resistance Polymer/glass (UNDER WATER ONLY) with 100 W halogen bulb for 12V step down transformer . with Brackets SS screws for Wall mounting, (LYXAR- Australia, OR EQUIVALENT).<br>With 2M cable for connections.<br>① transformer<br>② Pipe & fitting | 4 NOS<br>@ 6500/-<br>Each ✓ | Rs 26000 ✓<br>8000<br>20,000 |
| 6            | <b><u>ERECTION, TESTING , COMMISSONING OF THE FILTER, PUMPS ETC.</u></b>                                                                                                                                                                                                                                                        | L.S                         | Rs 30,000<br>25,000/-        |
| <b>TOTAL</b> |                                                                                                                                                                                                                                                                                                                                 |                             | Rs 2,32,000.                 |

**TOTAL FOR ALL THE ABOVE EQUIPMENTS AND SERVICES WILL BE**  
**Rs 2,32,000-00**

2,13,000/-



## **pragati consultants**

**SWIMMING POOLS\*CONSULTANTS\*CONTRACTORS**

**L1.Lattitude Tower, Timberlake colony, Off Gachibowli road, Hyderabad 500008**

**Ph : 65702402, Mobile : 9848131574,**

**Email: pragatipools@gmail.com**

**WWW.PRAGATIPOOLS.COM**

---

**NOTE : CONSULTANCY /SITE VISIT CHARGES RS 35000/- EXTRA.**

**Terms and conditions :**

**Payment Terms :**

- 1) 40% advance along with confirm order.
  - 2) 50% after filter, ladders, filter media is delivered at the site
  - 3) 10% after erection testing and commissioning
- ❖ The above quotation for treatment plant does not include any civil works like fixing of bars, ladders, diving boards etc., for which only guidance and supervision will be given for fixing.
  - ❖ GST extra at 18 % of the work order (works contract tax)
  - ❖ Power supply should be made available in the filter plant room.
  - ❖ Filter plant will delivered in coordination with the progress of civil works.
  - ❖ This quotation is valid for a period of 1 months only
  - ❖ One year warranty on all items from the date of erection and commissioning.

Thanking you,

**For PRAGATI CONSULTANTS**

**(DHEERAJ ANANTHOJ).**

T.O.  
M.D.

| Comparative Statement |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |                                    |               |                                                            |                        |                                                             |                        |                                             |                       |
|-----------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|------------------------------------|---------------|------------------------------------------------------------|------------------------|-------------------------------------------------------------|------------------------|---------------------------------------------|-----------------------|
| Gallons               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | VISTA |      |                                    |               | BNC                                                        |                        | SERENE                                                      |                        | SERENE - Villa no. 17                       |                       |
| S.No.                 | Particulars                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Units | Qty  | 22500 gallons<br>Unit Price<br>Rs. | Amount<br>Rs. | Particulars                                                | Amount<br>Rs.          | Particulars                                                 | Amount<br>Rs.          | Particulars                                 | Amount<br>Rs.         |
| 1)                    | <b>Filter Circulation System:</b><br>Consisting of 1 No. Compact polyster FRP<br>Pressure filter of Diameter 900mm with inlet and outlet for the<br>the filtered water with the under collection piping hub with laterals<br>for water outlet with max working pressure upto 10 bars,<br>with the shell made of high grade polyster +FRP(Laminated).<br>with filtration rate of 50M3/HR/M2.<br>Max. Flow rate upto 40m3/HR (MIDAS/CWG/MINDER)<br>Including Multi port valve for filter/Connectors.<br><b>Multi port valve for Filter/Connectors: 1 SET</b><br>A 6 way rotary multiport valve with single lever operation for Filter/<br>Backwash/Rinse/Waste/Closed functions with Unions, Connectors,<br>Pressure guage, Level indicator made of High Grade ABS<br>(ACRYLONITRILE BUTADIENE STYRENE) plastic - Midas<br><b>Filter Media(White Quartz Sand) - 400KGS</b><br>16/30 Sieve size uniform grade for effective filtration @15/- per kg | L.S   | 1.00 | 85,000.00                          | 85,000.00     |                                                            | 90,000.00              |                                                             | 90,000.00              | FRP dia 800mm                               | 80,000.00             |
| 2)                    | <b>Circulation Pump / Starter / Prefilter</b><br>Supply and plumbing connections for 3HP<br>Monoblock pump set of Kirloskar - SP 2HM model(Self Priming),<br>Discharge - 25m3/hr - 35m3/hr<br>Including L & T starter.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Nos.  | 1.00 | 25,000.00                          | 25,000.00     | Model SP2HM<br>Discharge 25m3/hr - 30m3/hr<br>Head - 5mtrs | 35,000.00              | Model KDS335<br>Discharge 20m3/hr - 25m3/hr<br>Head - 7mtrs | 30,000.00              | Model SP1HM<br>Discharge 15M3/hr<br>20M3/HR | 26,500.00             |
| 3)                    | <b>Inlet Nozzle / Shell Fittings / Drains</b><br>ABS Surflow Inlet Nozzle, Anti Vortex and other fittings<br>and connectors.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | L.S.  | 1.00 | 5,000.00                           | 5,000.00      |                                                            | 15,000.00              |                                                             | 15,000.00              |                                             | 3,000.00              |
| 4)                    | <b>Suction / Vaccum Sweeping Head:</b><br>Brush head made of SS(316) Sheet metal 2mm thick with PP<br>(Replacable brushes) with black tough plastic bristles along with<br>the Hose Pipe. Including the required fittings and connectors to<br>the pump(with hose pipe) and SS handle(6mm).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | L.S.  | 1.00 | 30,000.00                          | 30,000.00     |                                                            | 35,000.00              |                                                             | 35,000.00              |                                             | 28,000.00             |
| 5)                    | <b>SS Pool Ladder / Grab Rails(SS316 pipe / sheet):</b><br>With mirror finish, steps, sheet beded, SS nut bolts fastened steps<br>with MS flat for fastened and permanent grouting<br>SS Ladder<br>Grabrails                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | nos   | 2.00 | 15,500.00                          | 31,000.00     | 2nos x 20,000/-<br>10nos x 2,200/-                         | 40,000.00<br>22,000.00 | 2nos x 20,000/-<br>8nos x 2,200/-                           | 40,000.00<br>17,600.00 | 1 no x 16500<br>4 nos x 2000                | 16,500.00<br>8,000.00 |
| 6)                    | <b>Supply of Pool maintainance items/chemicals:</b><br>Hand brushes, Manual cleaning long Brush, (Algae), Polyvinyle<br>Deep bag net, Test kit and pool chemicals(for commissioning only)<br>TCCA-90 Granuals, Alum, Soda ash                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | set   | 1.00 | -                                  | -             |                                                            | 5,000.00               |                                                             | 5,000.00               |                                             | -                     |
| 7)                    | <b>Pipes/Fittings for filter connections:</b><br>Pipes/Fittings, Ball valves, NRV etc, required for all the required<br>connections tobe made from the pool to the filter and back.<br>(Assuming the Filter, pumps are not more than 5M from the pool<br>surrounding), (UPVC SCH 40, Fittings SCH 80). 10KGF                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | set   | 1.00 | -                                  | -             |                                                            | 35,000.00              |                                                             | 25,000.00              |                                             | 20,000.00             |
| 8)                    | <b>Technical services, Plumbing, Erection, Testing, Commissionings:</b><br>Site visits for civil works, Drawings, Filter pump, Inlets, Drains and<br>Erection filters, pumps and comissioning of the Filter Circulation<br>system.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | L.S.  | 1.00 | 20,000.00                          | 20,000.00     |                                                            | 30,000.00              |                                                             | 30,000.00              |                                             | 25,000.00             |

T.O. & free of charge

|                       |                                                                                                                                                                                                                                                                               |     |      |          |                    |                                   |                    |                                  |                    |              |                    |
|-----------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|------|----------|--------------------|-----------------------------------|--------------------|----------------------------------|--------------------|--------------|--------------------|
| 9)                    | <b>Under Water Lighting Fixtures:</b><br>High Temperature Resistance Polymer/Glass(Under water only)<br>with 100W halogen bulb for 12V step down transformer with<br>brackets SS screws for wall mounting.<br>(LYXAR - Australia / Equivalent) with 2M cable for connections. | Nos | 6.00 | 5,500.00 | 33,000.00          | 10nos x 6,000/-<br>12W LED Lights | 60,000.00          | 8nos x 6,000/-<br>12W LED Lights | 48,000.00          | 4 nos x 6500 | 26,000.00          |
| 10)                   | <b>Transformer for the lights(EN 60742) 230v/12v:</b><br>Supply of step down transformer for the lights 230V/12V supply<br>for the under water lights                                                                                                                         | set | 1.00 | -        | -                  | SMPS for LED                      | 24,000.00          | SMPS for LED                     | 17,000.00          |              | 8500               |
| 11)                   | Consultancy Charges                                                                                                                                                                                                                                                           | -   | -    | -        | 35,000.00          |                                   | 40,000.00          |                                  | 40,000.00          |              | 25,000.00          |
|                       | <b>Total Amount</b>                                                                                                                                                                                                                                                           |     |      |          | <b>2,76,000.00</b> |                                   | <b>4,31,000.00</b> |                                  | <b>3,92,600.00</b> |              | <b>2,13,000.00</b> |
| *Note: GST extra @18% |                                                                                                                                                                                                                                                                               |     |      |          |                    |                                   |                    |                                  |                    |              |                    |

T.D. Monteeey  
21/1/18

2,66,000  
P.D. 15/1/18

*Duplicate*

## pragati consultants

SWIMMING POOLS\*CONSULTANTS\*CONTRACTORS

L1.Lattitude Tower, Timberlake colony, Gachibowli road, Hyderabad 500008

Ph : 65702402, Mobile : 9848131574, .

Email: pragatipools@gmail.com

WWW.PRAGATIPOOLS.COM

TO,

SERENE CONSTRUCTIONS LLP

C/O MPIPL,

M.G ROAD

SECUNDRABAD.

DATE: 27 /02/19

KIND ATTN: MR. SOHAM MODI

SUB: DELIVERY OF SWIMMING POOL EQUIPMENTS AT

VILLA @ SERENE FARMS- REG

Sir,

As per the W.O dated 08/02/19 for the swimming pool filter equipments

We have Delivered the same at the site

Hence we request you to please kindly release the next payment of (45%) **Rs 1,41,246-00.**

We are here by furnishing the details of the payments received by us till date.

TOTAL AS PER INVOICE (DATED 27-02-19)

Rs 3,13,880-00

### PAYMENTS RECEIVED:

|                                                  |              |
|--------------------------------------------------|--------------|
| 1) Advance Chq no: 127128 YES BANK Dated /2/19 . | Rs 49,000-00 |
| 2) Advance Chq no: 127129 YES BANK Dated /2/19 . | Rs 49,000-00 |
| 3) Advance Chq no: 127130 YES BANK Dated 2/19 .  | Rs 6,272-00  |

TOTAL RECIEVED

Rs 1,04,272-00

BALANCE

Rs2,09,608 -00

Please kindly do the needful and arrange for the payment at the earliest.

THANKS & REGARDS

For PRAGATI CONSULTANTS



(DHEERAJ ANANTHOJ).



| INWARD                  |                                                                                             |
|-------------------------|---------------------------------------------------------------------------------------------|
| Inward No: 4118         | Dt: 27-02-19                                                                                |
| MRN No:                 | Dt:                                                                                         |
| Received By: Mukul      | Sign:  |
| Serene Construction (Hy |                                                                                             |



# pragati consultants

**SWIMMING POOLS\*CONSULTANTS\*CONTRACTORS**

L1.Lattitude Tower, Timberlake colony, Gachibowli road, Hyderabad 500008

Ph : 65702402, Mobile : 9848131574, .

Email: pragatipools@gmail.com

WWW.PRAGATIPOOLS.COM

## TAX I N V O I C E / B I L L

Date : 27 -02-19

OUR GST NO :36 ACWPA0921A1Z4

Invoice no : PC/ 2019/02/1


CONSIGNEE GSTN:

Consignee : SERENE CONSTRUCTIONS LLP- SERENE FARMS, Yenkepally.

Work order Dated: 08/02/2019.

| Sl. No. | Description                                                                                                                                                                       | UOM  | BOQ | Unit Rate (In Rs.) | Amount (In Rs.) |
|---------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-----|--------------------|-----------------|
| 1       | <b><u>FILTER CIRCULATION SYSTEM/PRESSURE SAND FILTER</u></b><br>Consisting of a Compact FRP Pressure filter of Diameter 800mm . F/R -40M3/HR<br>MFR- 30M3/HR                      | Nos. | 1   | 80,000.00          | 80,000.00       |
|         | <b><u>MULTI PORT VALVE FOR FILTER./ CONNECTOR. 6 WAY,ABS ,MIDAS- GERMANY.</u></b><br><b><u>FILTER MEDIA WHITE QUARTZ SAND</u></b><br>16/30 sieve size uniform grade.              |      |     |                    |                 |
| 2       | <b><u>RECIRCULATION PUMPS</u></b><br>Supply and plumbing connections for 2HP monoblock pump set of Kirloskar SP1 HM series make capable of delivering 15M3/H 20M3/Hwater.         | Nos. | 1   | 26500.00           | 26500.00        |
| 3       | <b><u>INLET NOZZLES/SHELL FITTINGS</u></b><br>SURFLOW NOZZLES,DRAINS,VACCUM POINTS                                                                                                | SET  | 1   | 3000.00            | 3000.00         |
| 4       | <b><u>SUCTION SWEEPER HEAD(SS) 316,</u></b><br>One portable suction sweeper equipment comprising of SS brush head 20"with flexible hose pipe 30 M connected to the pump , Handle. | SET  | 1   | 28000.00           | 28000.00        |

| INWARD                   |                   |
|--------------------------|-------------------|
| Inward No: 4112          | Dt: 27-02-19      |
| MRN No:                  | Dt.               |
| Received By: Mukul       | Sign: [Signature] |
| Serene Construction (Hy) |                   |




|                                |                                                                                                                                                                                                                                                                                                          |     |   |          |                      |
|--------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|---|----------|----------------------|
| 5                              | <b>POOL LADDER S.S (316) ,<br/>Flat steps,with flat for fastening.</b>                                                                                                                                                                                                                                   | Nos | 1 | 16500.00 | 33000.00             |
|                                | <b>GRAB BARS</b>                                                                                                                                                                                                                                                                                         | Nos | 4 | 2000.00  | 8000.00              |
| 6                              | <b>Supply of Underwater light fixtures.</b> High<br>Temperature Resistance Polymer/glass<br>(UNDER WATER ONLY) with 12 W LED<br>for12V step . with Brackets SS screws for<br>Wall mounting, (LYXAR- Australia, OR<br>EQUIVALENT).<br>With 2M cable for connections.<br>.1) Transformer- EN60742-230V/12V | Nos | 4 | 6500.00  | 26000.00             |
|                                | 2)PIPES FOR FILTER CONNECTIONS                                                                                                                                                                                                                                                                           | Nos | 1 | 8000.00  | 8000.00              |
|                                |                                                                                                                                                                                                                                                                                                          | L.S |   | 20000.00 | 20000.00             |
|                                | <b>TECH,PLUMBING, ERECTION ,TESTING<br/>,COMMISSIONING</b><br>For connections of filter, PUMPS,INLETS,<br>DRAINS ETC.                                                                                                                                                                                    | JOB | 1 | 25000.00 | 25000.00             |
| 8                              | <b>CONSULTANCY CHARGES</b>                                                                                                                                                                                                                                                                               | L.S | 1 | 25000.00 | 25000.00             |
| <b>TOTAL :</b>                 |                                                                                                                                                                                                                                                                                                          |     |   |          | <b>2,66,000.00</b>   |
| <b>ADD SGST @ 9 %</b>          |                                                                                                                                                                                                                                                                                                          |     |   |          | <b>23940.00</b>      |
| <b>ADD CGST @ 9 %</b>          |                                                                                                                                                                                                                                                                                                          |     |   |          | <b>23940.00</b>      |
| <b>FINAL TOTAL AFTER TAXES</b> |                                                                                                                                                                                                                                                                                                          |     |   |          | <b>Rs3,13,880.00</b> |

(TOTAL RUPEES THREE LAKH THIRTEEN THOUSANDS EIGHTY EIGHTY ONLY)

For PRAGATI CONSULTANTS

| INWARD                  |                   |
|-------------------------|-------------------|
| Inward No: 4118         | Dt: 27-02-19      |
| MRN No:                 | Dt:               |
| Received By: Mukul      | Sign: [Signature] |
| Serene Construction (Hy |                   |



(DHEERAJ ANANTHOJ)

# WORK ORDER

Original Copy / Office Copy

To,

Dt: 08/02/2019

Pragati Consultants  
Mr.Dheeraj Ananthoj, Consultant Engineer  
# 23-06-87, Hari Bowli,  
Near Shali Bunda,  
Hyderabad-500 065.

Dear Sir,

Sub: Work Order for Swimming Pool equipments for our site  
**Villa no. 17, Serene Constructions LLP, Located at Yenkepally.**

Ref: 1) Your quotation dated: 08/09/2018  
2) Personal discussions & negotiations on dtd. 12/11/2018

Swimming Pool Capacity : 10' x 18' x 4' deep / 45,000 gallons(21M3)  
Turnover period : 1.5 Hrs(per cycle)  
P.S.F. Capacity : 1no x 50gpm(15m3/HR)

| S.No. | Particulars                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Units | Qty  | Unit Price<br>Rs. | Amount<br>Rs. |
|-------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|-------------------|---------------|
| 1)    | <b><u>Filter Circulation System:</u></b><br>Consisting of 1 No. Compact polyster FRP<br>Pressure filter of Diameter 800mm with inlet and outlet for the<br>the filtered water with the under collection piping hub with laterals<br>for water outlet with max working pressure upto 10 bars,<br>with the shell made of high grade polyster +FRP(Laminated).<br>with filtration rate of 40M3/HR/M2.<br>Max. Flow rate upto 30m3/HR.(MIDAS/CWG/MINDER)<br>Including Multi port valve for filter/Connectors.<br><b><u>Including Multi port valve for Filter/Connectors: 1 SET</u></b> | L.S   | 1.00 | 80,000.00         | 80,000.00     |
| 2)    | <b><u>Circulation Pump / Starter / Prefilter</u></b><br>Supply and plumbing connections for 2HP<br>Monoblock pump set of Kirloskar - SP 1HM model(Self Priming),<br>Discharge - 15m3/hr - 20m3/hr<br>Including L & T starter.                                                                                                                                                                                                                                                                                                                                                      | Nos.  | 1.00 | 26,500.00         | 26,500.00     |
| 3)    | <b><u>Inlet Nozzle / Shell Fittings / Drains</u></b><br>ABS Surflow Inlet Nozzle, Anti Vortex and other fittings<br>and connectors.                                                                                                                                                                                                                                                                                                                                                                                                                                                | L.S.  | 1.00 | 3,000.00          | 3,000.00      |
| 4)    | <b><u>Suction / Vaccum Sweeping Head:</u></b><br>Brush head made of SS(316) Sheet metal 2mm thick with PP<br>(Replacable brushes) with black tough plastic bristles along with<br>the Hose Pipe. Including the required fittings and connectors to<br>the pump(with hose pipe) and SS handle(6mm).                                                                                                                                                                                                                                                                                 | L.S.  | 1.00 | 28,000.00         | 28,000.00     |
| 5)    | <b><u>SS Pool Ladder / Grab Rails(SS316 pipe / sheet):</u></b><br>With mirror finish, steps, sheet beded, SS nut bolts fastened steps<br>with MS flat for fastened and permanent grouting<br>SS Ladder                                                                                                                                                                                                                                                                                                                                                                             | nos   | 1.00 | 16,500.00         | 16,500.00     |

|    |                                                                                                                                                                                                                                                            |      |      |           |                    |
|----|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------|-----------|--------------------|
|    | Grabrails                                                                                                                                                                                                                                                  | nos  | 4.00 | 2,000.00  | 8,000.00           |
| 6) | <b>Suppl of Underwater Light fixtures:</b>                                                                                                                                                                                                                 | nos  | 4.00 | 6,500.00  | 26,000.00          |
|    | High temperature resistance Polymer/glass(Under water only) with 100W Halogen bulb for 12V step down transformer with brackets SS screws for wall mounting(Lyxar - Australia or Equivalent) with 2M cable for connections.(Transformer with pipe fittings) |      |      |           |                    |
|    | 1) Transformer - EN 60742 - 230V/12V                                                                                                                                                                                                                       | nos  | 1.00 | 8,000.00  | 8,000.00           |
|    | 2) Pipe fittings for filter connection                                                                                                                                                                                                                     | L.S. | 1.00 | 20,000.00 | 20,000.00          |
| 7) | <b>Technical services, Plumbing, Erection, Testing, Commissionings:</b>                                                                                                                                                                                    | L.S. | 1.00 | 25,000.00 | 25,000.00          |
|    | Site visits for civil works, Drawings, Filter pump, Inlets, Drains and Erection filters, pumps and comissioning of the Filter Circulation System.                                                                                                          |      |      |           |                    |
| 8) | Consultancy charges                                                                                                                                                                                                                                        | L.S. | 1.00 | 25,000.00 | 25,000.00          |
|    | <b>Total amount</b>                                                                                                                                                                                                                                        |      |      |           | <b>2,66,000.00</b> |
|    | <b>(Rupees Two lakhs seventy six thousand only)</b>                                                                                                                                                                                                        |      |      |           |                    |

### Terms & Conditions:

- 1) a) 40% advance Rs. 1,06,400/-  
b) 45% after the first consignment of materials i.e. filter, filter media etc. delivered at the site.  
c) 15% after supply of pump, erection, testing and commissioning.
- 2) The above quotation for treatment plant does not include any civil works like fixing of bars, ladders, diving boards etc. for which only guidance and supervision will be given for fixing.
- 3) Pipe lines required for inlet and outlet connection will have to be arranged by us.
- 4) GST extra @ 18% of the work order value.
- 5) Power supply will be made available in the filter plant room
- 6) Filter plant will delivered in coordination with the progress of civil works.
- 7) Electrical connections/starter for the pump and light fixtures have to be arranged by us.
- 8) 1 Year Warranty on all items from the date of erection and commissioning.
- 9) Bill in the name of **Serene Constructions LLP**

Thanking you.

Yours truly,

**For Serene Constructions LLP**

**Mr. Soham Modi**  
**Managing Director**

Confirmed by :

Date :

Sign :

Serene Constructions LLP

# WORK ORDER

Original Copy / Office Copy

To,

Dt: 08/02/2019

Pragati Consultants  
Mr.Dheeraj Ananthoj, Consultant Engineer  
# 23-06-87, Hari Bowli,  
Near Shali Bunda,  
Hyderabad-500 065.

Dear Sir,

Sub: Work Order for Swimming Pool equipments for our site  
**Villa no. 17, Serene Constructions LLP, Located at Yenkepally.**

Ref: 1) Your quotation dated: 08/09/2018  
2) Personal discussions & negotiations on dtd. 12/11/2018

Swimming Pool Capacity : 10' x 18' x 4' deep / 45,000 gallons(21M3)  
Turnover period : 1.5 Hrs(per cycle)  
P.S.F. Capacity : 1no x 50gpm(15m3/HR)

APPROVED BY  
08 FEB 2019  
SUHAM MODI  
MANAGING DIRECTOR

| S.No. | Particulars                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Units | Qty  | Unit Price Rs. | Amount Rs.  |
|-------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|----------------|-------------|
| 1)    | <b><u>Filter Circulation System:</u></b><br>Consisting of 1 No. Compact polyster FRP Pressure filter of Diameter 800mm with inlet and outlet for the the filtered water with the under collection piping hub with laterals for water outlet with max working pressure upto 10 bars, with the shell made of high grade polyster +FRP(Laminated). with filtration rate of 40M3/HR/M2.<br>Max. Flow rate upto 30m3/HR.(MIDAS/CWG/MINDER)<br>Including Multi port valve for filter/Connectors.<br><b><u>Including Multi port valve for Filter/Connectors: 1 SET</u></b> | L.S   | 1.00 | 80,000.00      | ✓ 80,000.00 |
| 2)    | <b><u>Circulation Pump / Starter / Prefilter</u></b><br>Supply and plumbing connections for 2HP Monoblock pump set of Kirlskar - SP 1HM model(Self Priming), Discharge - 15m3/hr - 20m3/hr<br>Including L & T starter.                                                                                                                                                                                                                                                                                                                                              | Nos.  | 1.00 | 26,500.00      | ✓ 26,500.00 |
| 3)    | <b><u>Inlet Nozzle / Shell Fittings / Drains</u></b><br>ABS Surflow Inlet Nozzle, Anti Vortex and other fittings and connectors.                                                                                                                                                                                                                                                                                                                                                                                                                                    | L.S.  | 1.00 | 3,000.00       | ✓ 3,000.00  |
| 4)    | <b><u>Suction / Vaccum Sweeping Head:</u></b><br>Brush head made of SS(316) Sheet metal 2mm thick with PP (Replacable brushes) with black tough plastic bristles along with the Hose Pipe. Including the required fittings and connectors to the pump(with hose pipe) and SS handle(6mm).                                                                                                                                                                                                                                                                           | L.S.  | 1.00 | 28,000.00      | ✓ 28,000.00 |
| 5)    | <b><u>SS Pool Ladder / Grab Rails(SS316 pipe / sheet):</u></b><br>With mirror finish, steps, sheet beded, SS nut bolts fastened steps with MS flat for fastened and permanent grouting<br>SS Ladder                                                                                                                                                                                                                                                                                                                                                                 | nos   | 1.00 | 16,500.00      | ✓ 16,500.00 |

# Draft PO for Approval

|    |                                                                                                                                                                                                                                                                                                                                                                                                     |             |                      |                                   |                                          |
|----|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|----------------------|-----------------------------------|------------------------------------------|
|    | Grabrails                                                                                                                                                                                                                                                                                                                                                                                           | nos         | 4.00                 | 2,000.00                          | ✓ 8,000.00                               |
| 6) | <b>Suppl of Underwater Light fixtures:</b><br>High temperature resistance Polymer/glass(Under water only)<br>with 100W Halogen bulb for 12V step down transformer with<br>brackets SS screws for wall mounting(Lyxar - Australia or Equivalent)<br>with 2M cable for connections.(Transformer with pipe fittings)<br>1) Transformer - EN 60742 - 230V/12V<br>2) Pipe fittings for filter connection | nos<br>L.S. | 4.00<br>1.00<br>1.00 | 6,500.00<br>8,000.00<br>20,000.00 | ✓ 26,000.00<br>✓ 8,000.00<br>✓ 20,000.00 |
| 7) | <b>Technical services, Plumbing, Erection, Testing, Commissionings:</b><br>Site visits for civil works, Drawings, Filter pump, Inlets, Drains and<br>Erection filters, pumps and comissioning of the Filter Circulation<br>System.                                                                                                                                                                  | L.S.        | 1.00                 | 25,000.00                         | ✓ 25,000.00                              |
| 8) | Consultancy charges                                                                                                                                                                                                                                                                                                                                                                                 | L.S.        | 1.00                 | 25,000.00                         | ✓ 25,000.00                              |
|    | <b>Total amount</b><br>(Rupees Two lakhs seventy six thousand only)                                                                                                                                                                                                                                                                                                                                 |             |                      |                                   | ✓ <b>2,66,000.00</b>                     |

## Terms & Conditions:

- 1) a) 40% advance Rs. 1,06,400/- ✓  
b) 45% after the first consignment of materials i.e. filter, filter media etc. delivered at the site.  
c) 15% after supply of pump, erection, testing and commissioning.
- 2) The above quotation for treatment plant does not include any civil works like fixing of bars, ladders, diving boards etc. for which only guidance and supervision will be given for fixing.
- 3) Pipe lines required for inlet and outlet connection will have to be arranged by us.
- 4) GST extra @ 18% of the work order value.
- 5) Power supply will be made available in the filter plant room
- 6) Filter plant will delivered in coordination with the progress of civil works.
- 7) Electrical connections/starter for the pump and light fixtures have to be arranged by us.
- 8) 1 Year Warranty on all items from the date of erection and commissioning.
- 9) Bill in the name of **Serene Constructions LLP**

Thanking you.

Yours truly,

For Serene Constructions LLP

Mr. Soham Modi  
Managing Director



Confirmed by :

Date :

Sign :

| Comparative Statement |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |               |      |                   |               |                                                            |               |                                                             |               |                                                         |               |
|-----------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|------|-------------------|---------------|------------------------------------------------------------|---------------|-------------------------------------------------------------|---------------|---------------------------------------------------------|---------------|
|                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | VISTA         |      |                   |               | BNC                                                        |               | SERENE                                                      |               | SERENE - Villa no. 17                                   |               |
|                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 22500 gallons |      |                   |               | 37500 gallons                                              |               | 35000 gallons                                               |               | 4500 gallons                                            |               |
| S.No.                 | Particulars                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Units         | Qty  | Unit Price<br>Rs. | Amount<br>Rs. | Particulars                                                | Amount<br>Rs. | Particulars                                                 | Amount<br>Rs. | Particulars                                             | Amount<br>Rs. |
| 1)                    | <b>Filter Circulation System:</b><br>Consisting of 1 No. Compact polyester FRP Pressure filter of Diameter 900mm with inlet and outlet for the filtered water with the under collection piping hub with laterals for water outlet with max working pressure upto 10 bars, with the shell made of high grade polyster +FRP(Laminated) with filtration rate of 50M3/HR/M2<br>Max. Flow rate upto 40m3/HR (MIDAS/CWG/MINDER)<br>Including Multi port valve for filter/Connectors.<br><b>Multi port valve for Filter/Connectors: 1 SET</b><br>A 6 way rotary multiport valve with single lever operation for Filter/ Backwash/Rinse/Waste/Closed functions with Unions, Connectors, Pressure guage, Level indicator made of High Grade ABS (ACRYLONITRILE BUTADIENE STYRENE) plastic - Midas<br><b>Filter Media(White Quartz Sand) - 400KGS</b><br>16/30 Sieve size uniform grade for effective filtration @15/- per kg | L S           | 1.00 | 85,000.00         | 85,000.00     |                                                            | 90,000.00     |                                                             | 90,000.00     | FRP dia 800mm                                           | 80,000.00     |
|                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |               |      |                   |               |                                                            |               |                                                             |               | Filtration rate of 40M3/HR/M2<br>Flow rate upto 30M3/HR |               |
| 2)                    | <b>Circulation Pump / Starter / Prefilter</b><br>Supply and plumbing connections for 3HP Monoblock pump set of Kirloskar - SP 2HM model(Self Priming), Discharge - 25m3/hr - 35m3/hr<br>Including L & T starter.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Nos.          | 1.00 | 25,000.00         | 25,000.00     | Model SP2HM<br>Discharge 25m3/hr - 30m3/hr<br>Head - 5mtrs | 35,000.00     | Model KDS335<br>Discharge 20m3/hr - 25m3/hr<br>Head - 7mtrs | 30,000.00     | Model SP1HM<br>Discharge 15M3/hr<br>20M3/HR             | 26,500.00     |
| 3)                    | <b>Inlet Nozzle / Shell Fittings / Drains</b><br>ABS Surflow Inlet Nozzle, Anti Vortex and other fittings and connectors.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | L.S           | 1.00 | 5,000.00          | 5,000.00      |                                                            | 15,000.00     |                                                             | 15,000.00     |                                                         | 3,000.00      |
|                       | <b>Suction / Vaccum Sweeping Head:</b><br>Brush head made of SS(316) Sheet metal 2mm thick with PP (Replacable brushes) with black tough plastic bristles along with the Hose Pipe Including the required fittings and connectors to the pump(with hose pipe) and SS handle(6mm).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | L.S.          | 1.00 | 30,000.00         | 30,000.00     |                                                            | 35,000.00     |                                                             | 35,000.00     |                                                         | 28,000.00     |
| 5)                    | <b>SS Pool Ladder / Grab Rails(SS316 pipe / sheet):</b><br>With mirror finish, steps, sheet beded, SS nut bolts fastened steps with MS flat for fastened and permanent grouting<br>SS Ladder<br>Grabrails                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | nos           | 2.00 | 15,500.00         | 31,000.00     | 2nos x 20,000/-                                            | 40,000.00     | 2nos x 20,000/-                                             | 40,000.00     | 1 no x 16500                                            | 16,500.00     |
|                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | nos           | 6.00 | 2,000.00          | 12,000.00     | 10nos x 2,200/-                                            | 22,000.00     | 8nos x 2,200/-                                              | 17,600.00     | 4 nos x 2000                                            | 8,000.00      |
| 6)                    | <b>Supply of Pool maintainance items/chemicals:</b><br>Hand brushes, Manual cleaning long Brush, (Algae), Polyvinyle Deep bag net, Test kit and pool chemicals(for commissioning only)<br>TCCA-90 Granuals, Alum, Soda ash                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | set           | 1.00 | -                 | -             |                                                            | 5,000.00      |                                                             | 5,000.00      |                                                         | -             |
| 7)                    | <b>Pipes/Fittings for filter connections:</b><br>Pipes/Fittings, Ball valves, NRV etc, required for all the required connections tobe made from the pool to the filter and back.<br>(Assuming the Filter, pumps are not more than 5M from the pool surrounding), (UPVC SCH 40, Fittings SCH 80). 10KGF                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | set           | 1.00 | -                 | -             |                                                            | 35,000.00     |                                                             | 25,000.00     |                                                         | 20,000.00     |
| 8)                    | <b>Technical services, Plumbing, Erection, Testing, Commissionings:</b><br>Site visits for civil works, Drawings, Filter pump, Inlets, Drains and Erection filters, pumps and comissioning of the Filter Circulation System.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | L.S.          | 1.00 | 20,000.00         | 20,000.00     |                                                            | 30,000.00     |                                                             | 30,000.00     |                                                         | 25,000.00     |
| 9)                    | <b>Under Water Lighting Fixtures:</b><br>High Temperature Resistance Polymer/Glass(Under water only) with 100W halogen bulb for 12V step down transformer with                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Nos           | 6.00 | 5,500.00          | 33,000.00     | 10nos x 6,000/-<br>12W LED Lights                          | 60,000.00     | 8nos x 6,000/-<br>12W LED Lights                            | 48,000.00     | 4 nos x 6500                                            | 26,000.00     |

  
12/11

|                                                                                                          |                                                                                                                                                |     |      |  |  |  |              |             |              |
|----------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------|-----|------|--|--|--|--------------|-------------|--------------|
| brackets SS screws for wall mounting,<br>(LYXAR - Australia / Equivalent) with 2M cable for connections. |                                                                                                                                                |     |      |  |  |  |              |             |              |
| 10)                                                                                                      | Transformer for the lights(EN 60742) 230V/12V:<br>Supply of step down transformer for the lights 230V/12V supply<br>for the under water lights | set | 1.00 |  |  |  | SMPS for LED | 24,000.00   | SMPS for LED |
| 11)                                                                                                      | Consultancy Charges                                                                                                                            |     |      |  |  |  |              | 17,000.00   |              |
| Total Amount                                                                                             |                                                                                                                                                |     |      |  |  |  |              | 40,000.00   | 40,000.00    |
|                                                                                                          |                                                                                                                                                |     |      |  |  |  |              | 4,31,000.00 | 3,92,600.00  |
|                                                                                                          |                                                                                                                                                |     |      |  |  |  |              | 35,000.00   | 25,000.00    |
|                                                                                                          |                                                                                                                                                |     |      |  |  |  |              | 2,76,000.00 | 2,66,000.00  |

\*Note: GST extra @18%

*12/11*

*186*

APPROVED BY  
93 JAN 2019  
MANAGING DIRECTOR

*not Bert. under pol. and issue pol.*

File

Severe Pool

NO

DATE

10/8/15

Severe - Villa.

Swimming pool. - Discussion with the owner

Pool size  $18' \times 10' \times 6' = 1080 \text{ cu ft}$

$= 20,160$

$\approx 20 \text{ k ltr.}$

Filteration plant. —

① Conventional filter.

= Filter & pump — 90,000/-

- Ladder — 15,000/-

- Light  $4 \times 6,000/- = 24,000/-$

- Pumping — 10,000/-

- Civil work cost — 1.5 lac with  
conventional tiling.

Mosai: Men ~~cost~~ extra:

\* Filter to run for 1 hr a day.

\* Annual cost R. 2,000/-

# **WORK ORDER** Original Copy / Office Copy

To,

Dt: 08/06/2018

Pragati Consultants  
Mr.Dheeraj Ananthoj, Consultant Engineer  
# 23-06-87, Hari Bowli,  
Near Shali Bunda,  
Hyderabad-500 065.

Dear Sir,

Sub: Work Order for Swimming Pool equipments for our site  
**Serene Constructions LLP, Located at Yenkepally.**

Ref: 1) Your quotation dated: 11/05/2018  
2) Personal discussions & negotiations on dtd. 25/05/2018

Swimming Pool Capacity : 50' x 28' x 4' deep / 35,000 gallons(158M3)  
Balcony tank capacity : 4.5M3(3-5% Max.)  
Turnover period : 6 Hrs(per cycle)  
Total system capacity : 162.5 M3  
P.S.F. Capacity : 1no x 100gpm(27m3/HR)

| S.No. | Particulars                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Units | Qty  | Unit Price<br>Rs. | Amount<br>Rs. |
|-------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|-------------------|---------------|
| 1)    | <b><u>Filter Circulation System:</u></b><br>Consisting of 1 No. Compact polyster FRP<br>Pressure filter of Diameter 900mm with inlet and outlet for the<br>the filtered water with the under collection piping hub with laterals<br>for water outlet with max working pressure upto 10 bars,<br>with the shell made of high grade polyster +FRP(Laminated).<br>with filtration rate of 50M3/HR/M2.<br>Max. Flow rate upto 40m3/HR.(MIDAS/CWG/MINDER)<br>Including Multi port valve for filter/Connectors.<br><b><u>Multi port valve for Filter/Connectors: 1 SET</u></b><br>A 6 way rotary multiport valve with single lever operation for Filter/<br>Backwash/Rinse/Waste/Closed functions with Unions, Connectors,<br>Pressure guage, Level indicator made of High Grade ABS<br>(ACRYLONITRILE BUTADIENE STYRENE) plastic - Midas<br><b><u>Filter Media(White Quartz Sand) - 400KGS</u></b><br>16/30 Sieve size uniform grade for effective filtration @15/- per kg | L.S   | 1.00 | 90,000.00         | 90,000.00     |
| 2)    | <b><u>Circulation Pump / Starter / Prefilter</u></b><br>Supply and plumbing connections for 3HP<br>Monoblock pump set of Kirloskar - SP 2HM model(Self Priming),<br>Discharge - 25m3/hr - 35m3/hr<br>Including L & T starter.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Nos.  | 1.00 | 27,500.00         | 27,500.00     |
| 3)    | <b><u>Inlet Nozzle / Shell Fittings / Drains</u></b><br>ABS Surflow Inlet Nozzle, Anti Vortex and other fittings<br>and connectors.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | L.S.  | 1.00 | 6,000.00          | 6,000.00      |
| 4)    | <b><u>Suction / Vaccum Sweeping Head:</u></b><br>Brush head made of SS(316) Sheet metal 2mm thick with PP                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | L.S.  | 1.00 | 33,000.00         | 33,000.00     |

|    |                                                                                                                                                                                                                              |            |              |                       |                        |
|----|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|--------------|-----------------------|------------------------|
|    | (Replacable brushes) with black tough plastic bristles along with the Hose Pipe. Including the required fittings and connectors to the pump(with hose pipe) and SS handle(6mm).                                              |            |              |                       |                        |
| 5) | <b>SS Pool Ladder / Grab Rails(SS316 pipe / sheet):</b><br>With mirror finish, steps, sheet beded, SS nut bolts fastened steps with MS flat for fastened and permanent grouting<br>SS Ladder<br>Grabrails                    | nos<br>nos | 2.00<br>8.00 | 16,500.00<br>2,200.00 | 33,000.00<br>17,600.00 |
| 6) | <b>Supply of Pool maintainance items/chemicals:</b><br>Hand brushes, Manual cleaning long Brush, (Algae), Polyvinyle Deep bag net, Test kit and pool chemicals(for commissioning only)<br>TCCA-90 Granuals, Alum, Soda ash   | set        | 1.00         | 5,000.00              | 5,000.00               |
| 7) | <b>Technical services, Plumbing, Erection, Testing, Commissionings:</b><br>Site visits for civil works, Drawings, Filter pump, Inlets, Drains and Erection filters, pumps and comissioning of the Filter Circulation System. | L.S.       | 1.00         | 25,000.00             | 25,000.00              |
| 8) | Consultancy charges                                                                                                                                                                                                          | L.S.       | 1.00         | 40,000.00             | 40,000.00              |
|    | <b>Total amount</b><br><b>(Rupees Two lakhs seventy seven thousand one hundred only)</b>                                                                                                                                     |            |              |                       | <b>277,100.00</b>      |

#### **Terms & Conditions:**

- 1) a) 40% advance Rs. 1,10,840/-  
b) 45% after the first consignment of materials i.e. filter, filter media etc. delivered at the site.  
c) 15% after supply of pump, erection, testing and commissioning.
- 2) The above quotation for treatment plant does not include any civil works like fixing of bars, ladders, diving boards etc. for which only guidance and supervision will be given for fixing.
- 3) Pipe lines required for inlet and outlet connection will have to be arranged by us.
- 4) GST extra @ 18% of the work order value.
- 5) Power supply will be made available in the filter plant room
- 6) Filter plant will delivered in coordination with the progress of civil works.
- 7) Electrical connections/starter for the pump and light fixtures have to be arranged by us.
- 8) 1 Year Warranty on all items from the date of erection and commissioning.
- 9) Bill in the name of **Serene Constructions LLP**

Thanking you.

Yours truly,

**For Serene Constructions LLP**

**Mr. Soham Modi**  
**Managing Director**

Confirmed by :

Date :

Sign :

## Purchase Order

Page(s) 1 Of 1

02-08-2018 14:03:47

Original / Office Copy / Purchase Div.Copy

From Company : **Serene Constructions LLP**  
5-4-187/374,ii Floor,M.G.Road,Secunderabad-500 003.  
G S T No. : 36ACVFS7909P1ZV

| Supplier Details                                                                             |          |            |                         |
|----------------------------------------------------------------------------------------------|----------|------------|-------------------------|
| Pragati Consultants<br>#23-6-87, Hari Bowli, Hyderabad-500065.<br><br>65702402<br>9848131574 | 24522715 | Doc No     | 52102 9674              |
|                                                                                              |          | Doc Date   | 02-08-2018              |
|                                                                                              |          | Quote No   | Nil                     |
|                                                                                              |          | Quote Date | 25-05-2018              |
|                                                                                              |          | SupplyType | Supply And Installation |

Kind Attn : Mr.Dheeraj Ananthoj

Purchase Order for the Supply of following Items.

| Item Name                                                                                | Qty  | Rate     | Dis% | GST%  | Amount    |
|------------------------------------------------------------------------------------------|------|----------|------|-------|-----------|
| 1 4746 - Electrical - other - LED Lights - NA - nos<br>12W - with SMPS driver - 230V/12V | 8.00 | 6,800.00 | 0.00 | 18.00 | 64,192.00 |
| Total Order Value . . .                                                                  |      |          |      |       | 64,192.00 |

Rupees : Sixty Four Thousand One Hundred Ninty Two Only.

### Terms and Conditions :-

|                       |                                                                                                                                                        |
|-----------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------|
| Specification / Brand | Item shall be of "LYXAR - Australia/ Equivalent brand. High temperature resistance polymer/glass with 100W halogen bulb for 12V step down transformer. |
| Payment Terms         | 40% as advance & balance 60% on completion of work.                                                                                                    |
| Tax                   | All taxes included in above price.                                                                                                                     |
| Delivery Date         | Within 4days.                                                                                                                                          |
| Delivery Location     | Serene Farms<br>Sy no-44, Yenkepally Village, Chevella Mandal,RR.Dist-501 503<br>Phone. ..                                                             |
| Penalty For Delay     | Nil                                                                                                                                                    |
| Transportation Cost   | Included in the above price.                                                                                                                           |
| Warranty              | 1year warranty on lights only.                                                                                                                         |
| Advance Paid          | Rs. 25,677/- advance to be pay vide cheque no. , dtd.                                                                                                  |
| Other Terms           | We reserve the right to reject items not conforming to quality and specifications. Above order for Swimming pool lighting purpose.                     |
| Completion Date       | Nil                                                                                                                                                    |
| Measurment            | Nil                                                                                                                                                    |
| Security              | Nil                                                                                                                                                    |
| Remarks               |                                                                                                                                                        |

For **Serene Constructions LLP**

Authorised Signatory

Accepted the above Terms And Conditions

For **Pragati Consultants**

Name : \_\_\_\_\_

Name : \_\_\_\_\_

Date : \_\_/\_\_/\_\_

Contact - -