

Purchase Order

From Company : **M/s Silver Oak Realty**
5-4-187/3 & 4, II nd floor, Soham mansion M.G Raod,Secunderabad.
T I N No. : 36840298894

Supplier Details

POWERLITE GENERATOR SYSTEMS (P) LTD
Registered office # 7010, Emerald house, 1-7-264, S.D Road,
secunderabad-500003
040-6541 4100
92468 27120

Doc No	36937	40590
Doc Date	30-06-2016	
Quote No	871	
Quote Date	24-06-2016	
SupplyType	Supply And Installation	

Kind Attn : MR.Anand jodhani

Purchase Order for the Supply of following Items.

Item Name	Qty	Rate	Dis%	VAT%	Amount
1 5026 - Equipment - machinery - Generator - other - nos 15 KVA With AMF Panel	1.00	236850.00	0.00	0.00	236850.00
Total Order Value . . .					236850.00

Rupees : Two Lakh(s) Thirty Six Thousand Eight Hundred Fifty Only.

Terms and Conditions :-

Specification / Brand Above item of "Escorts" make, G-15 - II , 22 BHP water cooled.1500 RPM NTP Conditions, Alternator of "Kirloskar" make with Aucoustic enclosure as per quote.

Payment Terms 15% advance 75% on material ready with proforma invoice & balance 10% on commissioning.

Tax All taxes Included in the above prices.

Delivery Date Within 1-2 weeks from the date of PO with advance

Delivery Location Villas At Silver Creek
Sy. No. 74 & 75, Cherlapally, Hyd. Beside of Kingston PG college.
Phone. Contact: 9502177288/9502266233

Penalty For Delay Nil

Transportation Cost Included in the above price.

Warranty 24months from date of commissioning & 12 months panel board & battery.

Advance Paid Rs.35,527/- vide Cheq.No.000889 dt.30/06/16 of HDFC Bank .

Other Terms We reserve the right to reject items not conforming to quality and specifications. Installation included in the above price. The above order for 45A to 45 J purpose.

Completion Date within 5 days delivery of all materials at site

Measurement Nil

Security You shall be responsible for storing materials at site Lockable rooms will be provided by us.

1-2-16 } -1
1-2-17 } -1
1-2-18 } -2

For **M/s Silver Oak Realty**

Authorised Signatory

Accepted the above Terms And Conditions

For **POWERLITE GENERATOR SYSTEMS (P) LTD**

Name : _____

Name : _____

Date : ___/___/___



SHREE J & J ENGINEERS

Diesel Generators, Gas Generators, Duel Fuel Generators, Transformers & Cables Sales.

Ref: SJJE/0069/16-17/HYD

Date: 17/06/2016

M/s. Modi Properties
Ranigunj, Secundrabad, Telangana

Kind Attention: Mr.Hari Babu

Dear Sir,

Sub: Your requirement of 10 KVA III Ph D.G.Set -reg.

We would like to introduce ourselves as a **Authorised Sales Dealer** of leading manufacturer of Engines and Diesel Generating Sets in India "**Greaves Cotton Limited**" with single window warranty along with a very vast & prestigious client base.

We also enjoy the track record of executing our entire project with high customer satisfaction level.

These diesel engines have the reputation of being the most rugged diesel engines in the country. These diesel engines are also indigenous in their manufacture and thus offer you spares at very economical prices and also backed up by a wide network of spares and service dealers spread across the country to offer you excellent services.

We generally represent our subsidiary company **M/s. Crompton Greaves Limited** for Alternator.

We are enclosing our detailed offer along with the terms and conditions as below:-

Scope of supply as per Annexure 1.

Pricing as per Annexure 2.

Installation as per Annexure 3.

We sincerely look forward to the pleasure of receiving your valued order on which will have our best & prompt attention at all times.

Thanking you

Yours faithfully
For Shree J & J Engineers.

Authorised Signatory
Atmanand Biradar

Encl: As mentioned above



SHREE J & J ENGINEERS

Diesel Generators, Gas Generators, Dual Fuel Generators, Transformers & Cables Sales.

Anx-1

Specifications & Scope of Supply for 10Kva GREAVES POWER Sound-Proof DG set powered by Greaves G-15-II engine.

ENGINE

Greaves make model G-15-II With Latest CPCB-II compliant, Direct Injection, 2 cylinders, Compression Ignited, Turbo Charged, Water-Cooled diesel engine developing 21.6HP at 1500 rpm & complying with BS5514 / ISO 3046 standards.

Besides standard components, the engine will be complete with:

12 V electrical starting system consisting of Starter motor, Charging alternator & 1 no. 12 V 88 AH Battery.
Dry type Air cleaner with restriction indicator
In-line Bosch Fuel injection system with Mechanical Governor (Class A1 governing)
Spin-on Lube oil filter elements
Radiator, pusher fan & fan drive arrangement
Gear driven water pump
Sensors for Oil pressure, Coolant temperature & level.
First fill of Lube oil. (API CF4 grade, Greaves Maxtherm Lube.)

ALTERNATOR

Crompton Greaves /Suitable make 3 Phase, 4 Wire, Self excited, Self regulated Brushless Single Bearing Type, Class H insulated AC generator developing 10kVA / 8kW at 415 V, 0.8 PF (Lag) with IP23 protection.

ANX:1 CONTROL PANEL

Control panel is 16 / 14 gauge sheet steel fabricated, dust & Vermin proof & will be complete with internal wiring. The following Protection / Control / Display / Annunciation features are provided for the DG set.

- MCB of adequate rating
- Indicating lamps for DG ON & LOAD ON.
- Set of Current transformers
- Set of control fuses

Micro-processor based Integrated DG set Controller type PROCOM with built-in Remote Auto START / STOP facility mounted in the facia of the control panel with a large 2 Line LCD display panel with the following continuous scrolling features:



SHREE J & J ENGINEERS

Diesel Generators, Gas Generators, Duel Fuel Generators, Transformers & Cables Sales.

Display parameters	Audio-Visual warning	Shut-down with Audio-visual annunciation
Engine Oil pressure	Low Oil pressure	Low Oil Pressure
Coolant temperature	High Coolant temp.	High coolant temp.
Canopy temperature	High Canopy temp.	Low Fuel level
Fuel level Indication %	Low Battery Voltage	Engine Over speed
Battery Voltage	High Battery Voltage	Engine under speed
Battery cranking Voltage	Charging altr.failure	Low coolant level in radiator
Engine rpm	Low Fuel Level	Under voltage
DG set hours run		Over voltage
Gen.Volts (Phase-neutral & Phase-Phase)		Over frequency
Gen.Current (Amps.)		Under frequency
Gen.Frequency (Hz.)		
Power factor		
kWhr.		
Kw		

- The controller has data logging facility for the latest 50 faults recorded & option for RS232 / RS485 connectivity for remote monitoring / BMS integration

Sound-proof Acoustic Enclosure

The Engine, Alternator & Control Panel are housed in an acoustic enclosure which is both sound-proof & weather-proof and complying with the latest noise pollution norms of the Ministry of Environment & Forests & certified by the ARAI, Pune.

Engine & Alternator are mounted in the canopy through AVMs on fabricated under-base. Fuel tank is built-in with easy access for fuel fill and removal for cleaning & Fuel piping. Control panel is also housed inside the canopy with excellent visibility through a hardened glass inspection window.

Salient features of the Ready to Use DG set

The acoustic enclosure is manufactured with CNC / Laser machines with 1.6 mm CRCA steel with an aesthetically pleasing finish.

Rigorous pre-treatment of sheet metal parts with Nine-tank phosphating & Power coated with pure polyester based compound.

Extremely Compact. Lowest foot print / Space envelope.

Ideal for out-door installation due to excellent corrosion & UV resistance properties.



SHREE J & J ENGINEERS

Diesel Generators, Gas Generators, Dual Fuel Generators, Transformers & Cables Sales.

Long lasting Green passivated fasteners. Cast aluminium hinges & Stainless steel locks for long durability & ease of operation.

Acoustic insulation with Fire-retardant acoustic foam to better the statutory norms of 75 dB (A) at 1 m distance under Free-Field conditions.

Fully completed Exhaust piping & heavy duty residential silencer fitment.

Fully completed fuel piping

Complete with incoming Cabling from Alternator to Control panel.

DG Set data-10kva

Compliance Standards – Engine	BS 5514 / ISO 3046
Compliance Standards- Alternator	IS 4722 / BS 5000
Compliance standards – DG set	ISO 8728 / Noise pollution norms of MOEF & certified by ARAI,Pune.
DG set Rating	Prime rating as per ISO 8728. 10% overload provision available for intermittent periods.
Integral Fuel Tank Capacity	100 Litres
DG set Dimensions (L x W x H)	2000 x 950 x 1400 mm*
DG set Dry Weight (Aprx,)	650 kg.

Greaves G11 series fuel consumption on 100% load 2.5Ltrs (+/-5% tolerance)

Note: Genset should have minimum 30% load .Under load performance is not guaranteed

*Silencer dimensions are not included.



SHREE J & J ENGINEERS

Diesel Generators, Gas Generators, Dual Fuel Generators, Transformers & Cables Sales.

Anx-3

CUSTOMER's SCOPE OF WORK: (Our Engineer will provide all guidelines)

Unloading and positioning DG Set/Panel. Making civil foundation for canopied DG Set, trenches for cables. All minor & major Civil Works Welding and finishing of extended exhaust if any with necessary cladding and Supports. Supply and laying of Power and Control Cables from DG Panel to your load/changeover/distribution Panels with glands, gland plates etc on DG Panel and Alternator as recommended, with supply and fixing of end Terminations for the above Power and control cables. Supply and erecting earth pits 2 Nos. as well as supplying and interconnecting the earth pits with copper / GI Strips – as required. Supply of Water, Diesel, Lubricating Oils, Coolants & Load etc for commissioning and Regular Maintenance Spares. Any statutory approvals.

GENERAL TERMS & CONDITIONS – SUPPLY OF DG SETS:

1. PRICES:

Excise Duty, Education Cess on ED: Unless specifically mentioned, the prices quoted are exclusive of Excise Duty & CESS. In case you provide Form CT3 / ED exemption certificates, the excise duty will be Nil. In case of any change in ED , effective ED will be charged accordingly.

Sales Tax: Local / Central Sales Tax/ VAT extra as applicable. All statutory forms/ way bills are to be furnished in advance, failing which the materials will not be dispatched.

Entry Tax: If any applicable, will be to your account and has to be paid by you directly to the Sales Tax authorities.

Freight & Transit Insurance: Unless specifically mentioned, the prices quoted are Ex-Works. Based on the discussions, the material will be dispatched on any one of: Freight to Pay/ Paid basis. Unless specifically mentioned, unloading will not be in our scope. Insurance does not cover unloading of DG Set at your site. In case of dispatches made on Transit Insurance included basis, any damage should be intimated in writing to our Hyderabad office within 7 days failing which we will not be able to take up the claim with the insurance company. Such damaged materials will be replaced after we receive the insurance claim. In case of materials where transit insurance is covered by you, all damages are to be claimed by you directly and we will supply the material against payment from you. Damages to materials due to faulty unloading will be rectified at an extra price. All freight/ courier charges to rectify the same will be to your account.

Note: Any changes in the above statutes including VAT etc at the time of delivery/ dispatch will be to your account.

2. VALIDITY:

Our offer is valid for 30 days from the date of offer and subject to extension based on our written confirmation thereafter.

3. WARRANTY:

The DG Set is covered under our warranty as from the date of commissioning or dispatch or the first declared running hours, whichever occurs the earliest. The warranty does not cover: rubber components, consumable spares & batteries. This warranty is also subject to maintenance of the DG set as per manufacturers' recommendations like periodic maintenance, use of genuine spares/ authorized service dealers and use of Greaves Maxtherm lubricating oils. All warranty claims will be at the sole discretion of the respective manufacturers of the components and their decision after analysis of the defect will be final. The warranty implies that they will analyze the defect if any and rectify/ replace the component in a reasonable time. We



SHREE J & J ENGINEERS

Diesel Generators, Gas Generators, Duel Fuel Generators, Transformers & Cables Sales.

Anx-2 Price and technical Specifications

Srl No.	Description	Unit	Qty	Unit Rate (Rs.)	Total (Rs.)
1	Supply of 10KVA/ 8KW Diesel Generating Set as per enclosed scope in Annexure I comprising of:				
	Diesel Engine			10KVA	
	Alternator	each	1	247619.05	247619.05
	Acoustic Enclosure				
	Accessories				
2	Std Control Panel	each	1	0.00	Included
Total Basic Price is inclusive of ED					247619.05
VAT (present VAT is 5%)				Rate % 5%	12380.95
Freight included till site included					0.00
Grand Total					260000.00
Rounded Off					260000.00
Rs. Two Lakh Sixty Thousand Zero Hundred Only					
Warranty: 30 months from the date of supply or 24 months from date of commissioning or first 5000 running hours whichever is earlier subject to terms mentioned in general terms and conditions. Warranty for Panel is 12 months and for Batteries is 12 months from date of commissioning.					
Payment Terms: 30% as advance along with the order and balance 70% against readiness of material prior to dispatch.					
Delivery: within 3-4 Weeks from the date of confirmed order with advance					
Billing: From Hyderabad					
Entry Tax: if applicable payable to be paid by customer					
Unloading & positioning at site: By you					
Validity: 30 days from date of offer.					
Against 'C' Form CST @ 2% can be billed from AP/Karnataka; but CST way bill/Road permit and Transportation charges extra is to be provided by you.					



SHREE J & J ENGINEERS

Diesel Generators, Gas Generators, Dual Fuel Generators, Transformers & Cables Sales.

will not be responsible for any consequential losses or damages due to any delay on this account. All freight/ courier charges to rectify the same will be to your account.

4. DELIVERY PERIOD:

The delivery period for supply will be on ex-works basis, subject to force majeure conditions. All prices quoted are for delivery on Ex Work's basis and not at site. We will also not be responsible for any delayed deliveries by transporters actions.

5. PAYMENT TERMS:

30% Advance and balance 70% against proforma invoice against proof of dispatch.

6. ACOUSTIC ENCLOSURE: (FOR DG SETS ONLY)

As it is mandatory for the Acoustic enclosure to be supplied along with the DG set, kindly note the following:- The canopy design & dimensions will be CPCB type approved. The design and drawings are the exclusive and sole property of ours and their authorized OEA's. The same may not be provided to any customer. We will only provide a copy of the type approval certificates in case you requires. Canopies are suited for outdoor application. For indoor applications, you have to ensure proper air intake & throw from the canopy by providing suitable arrangements at site. Temperature rise of up to 7 deg C above ambient is allowable inside the canopy. In case of stringent ambient conditions like higher temperatures & altitudes, suitable de rating factors are to be applied. Design & Dimensions cannot be altered to suit site conditions. Sound Pressure Level will be 75 dB (A) in free field conditions, not site conditions.

7. SCOPE OF SUPPLY:

The scope of supply will be strictly as per the technical offer submitted. Any item not mentioned in the scope and required subsequently by you will be supplied at a mutually agreeable extra price. Please insist & confirm exact scope of supply before placement of order.

8. We will have the option of raising our invoices from any of our factories/ branches.

9. ORDER ACCEPTANCE:

On receipt of your order, we will send you an order acceptance. Kindly acknowledge the same as a token of acceptance since we will be able to start processing your order only from the date of receipt of signed and sealed accepted copy of order acceptance.

10) Dispute: - In the unlikely event of any dispute, the same will be under the jurisdiction of the courts in Hyderabad only.

SRI LAKSHMI AGENCIES

powerol
by Mahindra

103, GYAN ARCADE, Beside SHEESH MAHAL THEATRE, AMEERPET, HYDERABAD-500 016

Ph: 040 - 23741003 , Cell: 98482 91003 , 98480 21003

TO

Date: 20.06.2016

M/s.Modi Properties
Hyderabad

Dear Sir

Sub: Quotation for MAHINDRA POWEROL DIESEL GENERATOR

We thank you for your enquiry. We have pleasure in giving below our offer. MAHINDRA POWEROL BRAND diesel generating sets Ready to use (RTU) type with 1500/3000 rpm, 220 V, Single Phase, 0.8 PF @NTP Conditions with standard accessories such as 25/90 Litres Fuel Tank, Fuel Piping, Silencer Exhaust Piping standard manual control panel with EPU, Power Cabling from alternator to control pannel, battery, duly charged with battry cables and first fill of lub oil.

S.NO	ENGINE MODEL	RATING	BHP	COOLING	PRICE
1	2185GM 3Ph	10KVA	18	LIQUID	229900/-
2	2185GM 1Ph	10KVA	18	LIQUID	236000/-

TERMS & CONDITIONS

- PRICE** : The above Price is Inclusive of all Taxes.
- ORDER** : The order should be in favor of M/s.SRI LAKSHMI AGENCIES, HYDERABAD with advance payment Cheque / D.D. In case of cancellation 15% value of the order will be forfeited.
- DELIVERY** : We anticipate to supply / dispatch within about 1~2 Weeks from the date of your technically and commercially clear Order.
- TRANSPORTATION** : Transportation & Unloading Charges Extra.
- PAYMENT** : 100% Advance by way of D.D./cheque in favour of M/s.Sri Lakshmi Agencies, Hyd.,
- WARRANTY** : 2years from the date of purchase. As per the company policy. & 6 Months guarantee for any complant without any questions asked.
- INSTALLATION** : Installation and Errection Charges are Extra as per the site requirement
- VALIDITY** : This Quotation is valid up to 30 Days.
- CIVIL WORKS** : Civil Bed&,Earth Pits are Not in our Scope
- COMMISSIONING** : Commissioning & Load Testing free of cost.

Lower

229,900
15
234,900

15 - *245,900*

We hope the above will suit your requirement, We ensure the best service at all times.

Thanking you,
Yours faithfully,

for Sri Lakshmi Agencies,

sd/- xxx
G S RAJU
Mob:9848021003

QUOTATION

24th June 2016

REF: PGS/DIR/QTN/871

To

Mr Hari Babu

Modi Properties

MG Road, Secunderabad

Ph: 9502277533, Email : haribabu@modiproperties.com

Site Incharge : Mr Purshotham Ph : 9502177288 Email : purshotham@modiproperties.com

Dear Sir

Sub: Quotation for 15 KVA TATA Escort Diesel Generator

15 KVA

In reference to your enquiry for 15 KVA DG Set with acoustic enclosure, we are glad to offer our prices along with terms & conditions

S. No	Description	Qty	Rate (Rs.)	Amount (Rs.)
1.	15 KVA Powerlite Genset model PLE15 <i>With Escorts engine CPCB 2 model G-15 developing 22 BHP, water cooled, coupled with Kirloskar make alternator 15 KVA (12 KW) Three phase, 415 V 1500 RPM. Control panel with electronic controller, Base frame, Fuel tank, and other accessories with acoustic enclosure as a complete set.</i>	1 set	2,15,000	2,15,000.00
2.	AMF Panel Controller for Auto Start/Stop & Line Voltage Monitoring	1 nos	12,000.00	12,000.00
	VAT		5%	11,350.00
	SUB TOTAL			2,38,350.00
	Freight & Unloading at site			3,000.00
	GRAND TOTAL			2,41,850.00

- Excise Duty : @ 12.5% Included in price
 Sales Tax : VAT@ 5% included as mentioned above
 Freight : Extra from factory in Jeedimetla, Hyderabad to site as mentioned above
 Warranty : 2 years or 3500 hours whichever is earlier

Note:

- The prices quoted are based on the present rates of excise duty, cess and sales Tax. Duties and taxes prevailing at the time of actual delivery will be applicable.

2. Delivery time mentioned in this quotation is subject to receipt of manufacturing inputs on time. No claim for damages, either direct or indirect, will be entertained on account of delays or failure to deliver the goods within the time stated above.
3. In case of any increases in price of alternator and or engine in the price will be revised and the same will be effective at the time of actual delivery irrespective of age of order or our delivery commitment or validity of our quotation.

TERMS & CONDITIONS	
DELIVERY	Within 1-2 weeks from the date of receipt of your technically/ commercially clear order along with advance.
PAYMENT	30% payment along with order and balance before delivery against proforma invoice.
VALIDITY	30 days and thereafter subject to our confirmation in writing

LIST OF EXCLUSIONS

The following are not in supply scope:

- Unloading and positioning at site
- Civil foundation
- Exhaust pipe extension and its insulation
- Earth pits and its interconnections
- All electrical related work like cabling and changeover switches
- Diesel for commissioning the DG Set
- Approval from electricity authority and all other statutory approvals
- Any other items which is not specifically included in our scope of supply

For any further clarifications please contact us

Thanking you

Yours faithfully,

Powerlite Generator Systems (P) Ltd

QUOTATION

24th June 2016

REF: PGS/DIR/QTN/871A

To

Mr Hari Babu

Modi Properties

MG Road, Secunderabad

Ph: 9502277533, Email : haribabu@modiproperties.com

Site Incharge : Mr Purshotham Ph : 9502177288 Email : purshotham@modiproperties.com

Dear Sir

Sub: Quotation for 10 KVA TATA Escort Diesel Generator

In reference to your enquiry for 10 KVA DG Set with acoustic enclosure, we are glad to offer our prices along with terms & conditions

10 KVA

S. No	Description	Qty	Rate (Rs.)	Amount (Rs.)
1.	10 KVA Powerlite Genset model PLE10 <i>With Escorts engine CPCB 2 model G-12 developing 18 BHP, water cooled, coupled with Kirloskar make alternator 10 KVA (8 KW) Three phase, 415 V 1500 RPM. Control panel with electronic controller, Base frame, Fuel tank, and other accessories with acoustic enclosure as a complete set.</i>	1 set	2,05,000	2,05,000.00
2.	AMF Panel Controller for Auto Start/Stop & Line Voltage Monitoring	1 nos	12,000.00	12,000.00
	VAT		5%	10,850.00
	SUB TOTAL			2,27,850.00
	Freight & Unloading at site			3,000.00
	GRAND TOTAL			2,30,850.00

- Excise Duty : @ 12.5% Included in price
 Sales Tax : VAT@ 5% included as mentioned above
 Freight : Extra from factory in Jeedimetla, Hyderabad to site as mentioned above
 Warranty : 2 years or 3500 hours whichever is earlier

Note:

- The prices quoted are based on the present rates of excise duty, cess and sales Tax. Duties and taxes prevailing at the time of actual delivery will be applicable.

2. Delivery time mentioned in this quotation is subject to receipt of manufacturing inputs on time. No claim for damages, either direct or indirect, will be entertained on account of delays or failure to deliver the goods within the time stated above.
3. In case of any increases in price of alternator and or engine in the price will be revised and the same will be effective at the time of actual delivery irrespective of age of order or our delivery commitment or validity of our quotation.

TERMS & CONDITIONS	
DELIVERY	Within 1-2 weeks from the date of receipt of your technically/ commercially clear order along with advance.
PAYMENT	30% payment along with order and balance before delivery against proforma invoice.
VALIDITY	30 days and thereafter subject to our confirmation in writing

LIST OF EXCLUSIONS

The following are not in supply scope:

- Unloading and positioning at site
- Civil foundation
- Exhaust pipe extension and its insulation
- Earth pits and its interconnections
- All electrical related work like cabling and changeover switches
- Diesel for commissioning the DG Set
- Approval from electricity authority and all other statutory approvals
- Any other items which is not specifically included in our scope of supply

For any further clarifications please contact us

Thanking you

Yours faithfully,

Powerlite Generator Systems (P) Ltd

Date	25.06.16		
Prepared by	Hari babu		
Subject	Comparative statement of 10 KVA Generator with AMF pannel		
	Greaves cotton	Mahindra	Tata Generator
Engine	Greaves cotton G-15 II 21.6 HP1500 RPM Radiator cooled	Mahindra 2185GM 1500 RPM Radiator cooled	Escort G-12 18 BHP Water cooled
Alternator	Crompton Greaves	Crompton	Kirloskar
Warrenty	24 months For Engine & alternator pannel & Batterys - 12 Months	24 months For Engine & alternator pannel & Batterys - 12 Months	24 months For Engine & alternator pannel & Batterys - 12 Months
Paymnets	15%+75%+10%	30%+70%	30%+70%
10 KVA with Amf panal	Rs: 2,40,000/-	Rs: 2,34,900/-	Rs : 2,30,850/-
15 KVA with Amf panal	Rs : 2,60,000/-	Rs : 2,50,900/-	Rs : 2,41,850/-
	Above prices F.O.R Site		



Close
2.35 lak
from purchase
Rs: 2.55,000/-

Final - 2.55,000/- 2.50,000/- 2,34,850
 Akhilesh buy 15 KVA Gen Delat Rs: 2,20,000/-
 without AMF

with AMF
 Total 10/2
 F.O.R. Site

To

MdS

Sub:- 15 KVA Generator

The above Generator the

Tata Generator given final price

is Rs: 2,36,850/- with AMF
panel, transportation, unloading & Commissioning

included in the above price.

This is for your approval.

Harsh
28/6/16

✓

APPROVED
29 JUN 2016
S. CHANDRASEKHAR
MANAGING DIRECTOR

Purchase Order

From Company : **Mehta and Modi Homes - Phase VII**
5-4-187/3 & 4, IInd floor, M.G.Road, Secunderabad - 500003
G S T No. : 36840298894

Supplier Details

SRI LAKSHMI AGENCIES
103,Gyan Arcade,Beside Sheesh Mahal Theatre,Ameetpet,Hyderabad.

040-23741003
98482-91003,9848021003

Doc No	24664	39847
Doc Date	03-06-2014	
Quote No	Nil	
Quote Date	20-05-2014	
SupplyType	Supply And Installation	

Kind Attn : Rajendra

Purchase Order for the Supply of following Items.

Item Name	Qty	Rate	Dis%	GST%	Amount
1 5026 - Equipment - machinery - Generator - other - nos 25 KVA	1.00	290,000.0	0.00	0.00	290,000.00
Total Order Value . . .					290,000.00

Rupees : Two Lakh(s) Ninty Thousand Only.

Terms and Conditions :-

Specification / Brand Above item of "Ashok Leyland"make,34.9HP @1500 RPM @ NTP Conditions,liquid cooled, Alternator of "Stamford" make.with AMF pannel +1 single contactor

Payment Terms 10% advance 60% on delivery of all material & balance 30% on commissioning.

Tax All Taxes Included

Delivery Date Within 1 week from the date of PO

Delivery Location Villas At Silver Creek
Sy. No. 74 & 75, Cherlapally, Hyd. Beside of Kingston PG college.
Phone. Contact: 9502177288/9502266233

Penalty For Delay Nil

Transportation Cost Included in the above price.

Warranty 24months on Engine/alternator/AMF, 1 year on Electrical parts

Advance Paid Rs.29000/- vide Cheq.No: 004097, dt: 03/06/14 of HDFC Bank

Other Terms We reserve the right to reject items not conforming to quality and specifications. The above order for site purpose.

Completion Date within 5 days delivery of all materials at site

Measurment Nil

Security You shall be responsible for storing materials at site Lockable rooms will be provided by us.

Remarks Nil

18.6.14
18.6.15
18.6.16
3.6.16

For **Mehta and Modi Homes - Phase VII**
Authorised Signatory

Accepted the above Terms And Conditions

For **SRI LAKSHMI AGENCIES**

Name : _____

Name : _____

Date : ___/___/___