

Original/Office Copy

Date: 11/01/2019.

From:  
M/s G V Research Centers PVT LTD,  
5-4-187/3&4, Iind floor, M.G.Road,  
Secunderabad

To,  
M/s Sree Nivasam Power Lines,  
Plot no. 94, Sri Ram Nagar, Kapra, ECIL post  
Hyderabad.  
GST - 36AKMPK7585Q1ZO.

Kind Attn.: Mr. P. Srinivas

### WORK ORDER

**Subject:** Confirmation of Work Order for LT & HT works on a turn key basis for our project G V Research Centers PVT LTD,  
Located at Aliabad.

Ref: 1) Your Quotation dtd. 07/12/2018.  
2) Approved quote by MD dtd. 08/01/2019.  
Dear Sir,

For G.V. RESEARCH CENTERS PVT. LTD.

Director

With reference to the above, we hereby award you the work order for the 20KW power supply works on a turn key basis as per the details mentioned below.

Sl. No.	Item Head	Item description	Quantity	Units	Rate Rs.	Item head amount Rs.
1	Liasoning	Liasoning , estimation, sanction and approval till the release of power as per the requirement.(No GST)	01	LS	1,00,000	1,00,000-00
2	Single pole structure consists (HT Line)	a) RS Joint (double pole welded) 9mtrs I.S.M.B. poles 1 no* 16,500/- b) H.T. Cross arm 3 nos* 1,000/- c) Pin insulator 3nos* 100/- d) 11KV Vertical type AB switch 200A 1no* 7,500/-(L & T make) e) 11KV H.G. Fuse set with required channels and hardware. 1 no* 3,500/- f) Mechanical protection for supporting of AB switch with clamps, painting and hardware 1no* 3,500/-(L & T make) g) 11KV disk & m/p 6nos* 350/- h) CI Pipes 3nos* 3,000/- i) Earth flat 10 nos in length* 100/- j) Bintonut powder 10bags* 200/- k) Earth wire 5gs* 50/- l) Distribution box 01 no* 2,500/- m) Nut bolts 5kgs* 60/- n) Lux & Tapes etc set* 1,000/- o) 35 x 3/5 Ug Lt cable 15mtrs* 176/- (Havells make) p) 55sq.mm conductor 110mtrs* 25/-(Havells make) q) Cable kis 2nos* 2,500/- r) Control box* 5,000/-(L & T make)	01	LS	50,000	50,000-00

For G.V. RESEARCH CENTERS PVT. LTD.

Director

3	Labour charges		01	LS	50,000	50,000-00
	Grand Total	(Rs. Two lakhs only)				2,00,000-00

Terms and conditions:

- a. Specifications:
  - i. Specification shall be as specified by electricity board from time to time.
- b. Payment terms:
  - i. Advance for sanction – Rs. 80,000/-
  - ii. Balance after complete delivery of all materials and completion of work.
- c. GST: Extra @18%

Please sign a copy of this letter as confirmation of your accepting the above terms and conditions.

Thank you,

Yours Sincerely,

For M/s G V Research Centers PVT LTD,

For G.V. RESEARCH CENTERS PVT. LTD.

Soham Modi Director  
Managing Director

Confirmed by M/s Sree Nivasam Power Lines

  
Signature:

Name: K. Srinivas  
Date: 18/01/2019

*Adm*

To

Dt:19-02-2019

MD sir

**Sub: - 25 KV Transform installation and commission works- Request for balance payment.**

The contractor sreenivasam power lines has completed installation and commission works of 25 KV transformer and connected load of 20 KV at GVRC site. The department has given connection on 18-02-2019. As per the PO we have to pay balance amount .The Balance Payment details:

(Rs)  
**Total invoice Amount : 2,35,723**  
**Including GST**

**Less Advance Paid : 80,000**  
-----

**Balance yet to pay : 1,55,723**  
-----

( one laksh fifty five thousand seven hundred twenty Three)


Herewith enclosed GST invoice and purchase order for your persual reference

please approve the above said amount

For G V Research Centers pvt., Ltd.,

*B. Sitaramanjani*  
B.Sitaramanjani  
Liasion manager

*W*  
**APPROVED BY**  
**25 FEB 2019**  
SUHAM MUJJI  
MANAGING DIRECTOR



# Sree Nivasam Power Lines

Reg.No. 841

'A' Grade Approved Contractor CPDCL

Electrical Engineers, Consultants, Pannel Boards, Transformers & Turnkey Projects

Invoice No :003

GSTIN No36AKMPK7585Q120

Date :19.11.19

M/s G.V Research Centers PVT LTD,5-4-187/374,2nd floor,M.G.Road, SecBad. GSTIN No36AAHCG4562D1ZP

SN o.	DESCRIPTION	HSN/SAC	QUANTITY	RATE	AMOUNT
1	.Ms pole	7216	1 nos	14,040.00	14,040.00
2.	Ab Switch	8535	1 nos	6,480.00	6,480.00
3	Ab Switch	8535	1 nos	6,480.00	6,480.00
4	Fabrication (2channel 3angle	7301	1 nos	960.00	960.00
5	Fabrication (guide angle)	7301	1 nos	180.00	180.00
6	C.I Pipe	7303	3 nos	1020.00	3,060.00
7	G I Patti (25x3mm)	7212	25 kg	86.00	2,150.00
8	G I Patti (Earth Coil)	7212	1 nos	120.00	120.00
9	Fabrication(Channel Cross Ar)	7301	2 nos	800.00	1,600.00
10	Fabrication(Channel(Middle Channel)	7301	1 nos	800.00	800.00
11	Fabrication(6/3 pole clamp)	7301	20 no	100.00	2,000.00
12	Fabrication(6/2 pole clamp)	7301	16 no	100.00	1,600.00
13	Nut & Bolts	7318	9 kg	100.00	900.00
14	M/S Box s/f box	7308	2 nos	2,000.00	4,000.00
15	34sq mm aaa conductor	7604	57 kg	185.00	10,545.00
16	AB Cable	8544	74 kg	200.00	14,800.00
17	MS Back Clamps	7308	35 kg	85.00	2,975.00
18	MS Stay Set	7308	5 nos	1000.00	5,000.00
19	50sqmm x 3 ½ Cable	8544	35 mt	200.00	7,000.00
20	70sqmm x 3 ½ Cable	8544	30 mt	300.00	9,000.00
21	Insulators 11kv Disk	8546	18 no	300.00	5,400.00
22	Insulators 11kv Pokymar Ins	8546	21 no	175.00	3,675.00
				<b>Total</b>	<b>1,02,765.00</b>
			<b>CGST</b>	9%	<b>9,248.85</b>
			<b>CGST</b>	9%	<b>9,248.85</b>
					<b>1,21,262.70</b>
23	Labour Charges				<b>97,000.00</b>
			<b>CGST</b>	9%	<b>8,730.00</b>
			<b>CGST</b>	9%	<b>8,730.00</b>
				<b>Total</b>	<b>2,35,722.70</b>



Proprietor.

NOTE

To

Dt: 09 -01 - 2019

MD sir

Sub: Advance to be released to the Contractor for getting sanction of 20 kw power supply at GVRC site- Reg.,

As per the Quotation conditions of the contractor of M/s Sree Nivasam Power Lines an advance 40% of the total quotation amount to be released alongwith confirmation. Quotation ~~of Rs.2.00~~ total approved amount Rs.2.00 lacs.

Out of Rs.2.00 lacs an amount of Rs.1.00 lac payment through cheque and Rs.1.00 lac through Cash.

Now The contractor is requesting to release Rs.40000/- cheque/online transfer and Rs.40000/-in cash i.e in total 40% of the quotation Amount.

This for your approval.

*Sitaraman,  
Co-ordinate with  
purchase for  
and release of  
advance  
w  
9/1/19*

*B*  
09/1/19  
B,Sitaramanjaneyulu  
Liasion manger

# SREE NIVASAM POWER LINES

'A' Grade Approved Contractors  
Plot no 94, Sri Ram Nagar, Kapra, ECIL Post, Hyd.  
Ph:9346613828  
GST – 36AKMPK7585Q1ZO

Ref.

Date : 07-12-2018

## QUOTATION

To

**G V ResearchCenters PVT Ltd,  
Aliabad Section**

Dear Sir,

Sub :- Quotation for Power Supply arrangement at your site – Reg.

We thank you very much for your enquiry and take pleasure to submit our lowest offer as details in the enclosed annexure.

## TERMS & CONDITIONS :

Taxes (GST)	:	18 % Extra on supply
Service Tax	:	--
Delivery	:	3– 5 weeks
Payment	:	Advance 40% along with confirmed P.O. under Progress 40%, remaining 20% after completion of work.
Transport	:	Inclusive
Exclusions	:	<b>Civil Works .SPDCL DD</b>

**ANNEXURE 1**

Sl.No.	DESCRIPTION OF MATERIALS	QTY.	MATERIAL	LABOUR	AMOUNT
02.	<b>Single Pole structure consists(HT Line)</b> a) RS joist (double pole welded)9mtr ✓ I.S.M.B. Poles 1 Nos. 16500/- ✓ b) H.T. Cross-arm 3 Nos* 1000/- ✓ c) Pin Insulators 3 Nos*100/- ✓ d) 11KV vertical type AB switch 200A 1 No. 7500/- — L&T ✓ e) 11 KV H.G.Fuse set with required channels and hardware. 1 Nos*3500/- ✓ f) Mechanical protection for supporting of AB Switch with clamps, painting & hardware 1No.3500/- — L&T ✓ g) 11kv disks&m/p 6 nos*350/- ✓ h) Ci pipes 3No*3000/- ✓ i) Earth flat 10 No Lenth*100/- ✓ j) Bitonut Powder 10Bags*200/- ✓ k) Earth Wire 5kg*50/- ✓ l) Distribution box 1No 2500/- — L&T ✓ m) Nut bolts 5kg*60/- ✓ n) Lux &Tapes etc set*1000/- ✓ o) 35 x3/5 Ug Lt cable 15 mtr x 176/- ✓ p) 55 sqmm conductor 110 mtrs x 25/- ✓ q) Cable kis 2 nos x 2500/- ✓ r) Control Box 5000/- — L&T ✓	L.S	50,840/-	50,000/-	
				Total	1,00,840=00

1. Material & Labour  
 2. Lisoning (non official)  
**TOTAL**

1,00,840=00 + 12%  
 1,00,000=00 - 100 GST.  
 2,00,840=00

Technically with above spec ✓  
 OK ✓  
 CA. Sinal ✓

2. off to be. 2 hour  
 Approved  
 8/1/19



Original/Office Copy/Purchase Div. Copy

Date: 10/01/2019.


From:  
M/s G V Research Centers PVT LTD,  
5-4-187/3&4, IInd floor, M.G.Road,  
Secunderabad

*Draft for  
MD  
Approved*



To,  
M/s Sree Nivasam Power Lines,  
Plot no. 94, Sri Ram Nagar, Kapra, ECIL post  
Hyderabad.  
GST – 36AKMPK7585Q1ZO.

Kind Attn.: Mr. P. Srinivas



*k*

WORK ORDER

**Subject:** Confirmation of Work Order for LT & HT works on a turn key basis for our project G V Research Centers PVT LTD,  
Located at Aliabad.

Ref: 1) Your Quotation dtd. 07/12/2018.  
2) Approved quote by MD dtd. 08/01/2019.

Dear Sir,

With reference to the above, we hereby award you the work order for the 20KW power supply works on a turn key basis as per the details mentioned below.

Sl. No.	Item Head	Item description	Quantity	Units	Rate Rs.	Item head amount Rs.
1	Liasoning	Liasoning , estimation, sanction and approval till the release of power as per the requirement.(No GST)	01	LS	1,00,000	1,00,000-00
2	Single pole structure consists (HT Line)	a) RS Joint (double pole welded) 9mtrs I.S.M.B. poles 1 no* 16,500/- b) H.T. Cross arm 3 nos* 1,000/- c) Pin insulator 3nos* 100/- d) 11KV Vertical type AB switch 200A 1no* 7,500/-(L & T make) e) 11KV H.G. Fuse set with required channels and hardware. 1 no* 3,500/- f) Mechanical protection for supporting of AB switch with clamps, painting and hardware 1no* 3,500/-(L & T make) g) 11KV disk & m/p 6nos* 350/- h) CI Pipes 3nos* 3,000/- i) Earth flat 10 nos in length* 100/- j) Bintonut powder 10bags* 200/- k) Earth wire 5gs* 50/- l) Distribution box 01 no* 2,500/- m) Nut bolts 5kgs* 60/- n) Lux & Tapes etc set* 1,000/- o)35 x 3/5 Ug Lt cable 15mtrs* 176/- (Havells make) p) 55sq.mm conductor 110mtrs* 25/-(Havells make) q) Cable kis 2nos* 2,500/-	01	LS	50,000	50,000-00

		r) Control box* 5,000/-(L & T make)				
3	Labour charges		01	LS	50,000	50,000-00
	Grand Total	(Rs. Two lakhs only)				2,00,000-00

Terms and conditions:

- a. Specifications:
  - i. Specification shall be as specified by electricity board from time to time.
- b. Payment terms:
  - i. Advance for sanction – Rs. 80,000/-
  - ii. Balance after complete delivery of all materials and completion of work.
- c. GST: Extra @18%

Please sign a copy of this letter as confirmation of your accepting the above terms and conditions.

Thank you,

Yours Sincerely,

For Paramount Estates, Gv RC Pvt Ltd.

Confirmed by M/s Sree Nivasam Power Lines

Soham Modi  
Managing Director

Signature:

Name:

Date: