

Company Name : Nilgiri Estate									
Details of extra soil quantity at Part-II									
Prepare by : Radheshyam									
Date : 29.05.17									
S.No.	Length	Units	Average in mtrs	Average in feet	Width	Units	Average in mtrs	Average in feet	Quantity in cft
1	182 Mtrs		160.6	526.76	142.5 Mtrs	138.86	455.47	1.45	347888.8969
2	163.5 Mtrs				133 Mtrs				
3	151 Mtrs				134.06 Mtrs				
4	145.9 Mtrs				145.9 Mtrs				
Deduction for road									
1	Main gate to part-I road		326 Feet	21 Feet	1.45 feet				9926.7 CFT
2	Villa no.100 to 118 road		421 Feet	21 Feet	1.45 Feet				12819.45 CFT
3	Villa no.136 to 152		493 Feet	21 Feet	1.45 Feet				15011.85 CFT
4	Villa no.81 to 88		364 Feet	24'9" Feet	1.45 Feet				13063.05 CFT
5	Villa no.91 to 99		409.5 Feet	24'9" Feet	1.45 Feet				14695.93 CFT
6	Villa no.100 to 101		91 Feet	24'9" Feet	1.45 Feet				3265.76 CFT
7	Villa no.135 to 136		91 Feet	24'9" Feet	1.45 Feet				3265.76 CFT
8	Villa no.119 to 120		108 Feet	29' Feet	1.45 Feet				4541.14 CFT
Total quantity :									
347888.8969									
(less) Total Roads deduction Villas deduction									
76589.64									
Total quantity :									
271299.2569 CFT									
Note : Roads contractor V.Mallalah ready to do the work for Rs.1.50/- cft									

NR