

aruna@modiproperties.com

Arun

From: "Soham Modi" <sohammodi@modiproperties.com>
Date: 31-03-2017 12:37 PM
To: <aruna@modiproperties.com>
Attach: Compound Estimate.xls
Subject: FW: Revised Estimate of Compound Miryalaguda

Print

From: Kirti Kumar [mailto:kirtikumar@modiproperties.com]
Sent: 31 03 2017 10:33
To: Soham Modi <sohammodi@modiproperties.com>
Cc: KARNA MEHTA <karnamehta@modiproperties.com>
Subject: Revised Estimate of Compound Miryalaguda

Please find the attachment of revised estimate of compound wall

Regards,

Y Kirti kumar

Project Manager | +91 95151 41674 | kirtikumar@modiproperties.com

Modi Properties & Investments Pvt. Ltd. | www.modiproperties.com

5-4-187/ 3 & 4, M G Road, Secunderabad - 03 | +91 40 66335551

Don't just buy a flat or villa! Buy a great lifestyle!

We build affordable flats & villas in gated communities

31-03-2017

ESTIMATE SHEET							
Company Name:		MRM LLP					
Project:		AGH					
Contractor Name							
Work Description:		RCC work of Compound wall					
Prepared By		Y Kirtikumar					
Date:		30/03/2016					
S No.	Item Head	Item Description	Quantity	Units	Rate	Total Amount	
	RCC Work	Excavation	61.25	Cft	6.00	367.50	
	(Total 213 Columns)	PCC	12.25	Sft	4.50	55.13	
		Footing	9.00	Cft	28.00	252.00	
		RCC Col below PB	4.00	Sft	25.00	100.00	
		Plinth Beam	10.00	Sft	25.00	250.00	
		RCC Col above PB	6.50	Sft	25.00	162.50	
			Total for 10 ft			1187.125	
			Total for / ft			118.7125	
			Say Per Rft			120.00	
			OR Per Set			1200.00	
			Total Of all Compound				
			1200x213			255600.00	

MEASUREMENT SHEET									
Company Name:		MRM LLP							
Project:		AGH							
Contractor Name									
Work Description:		RCC work of Compound wall							
Prepared By		Y Kirtikumar							
Date:		30/03/2016							
S No.	Item Head	Item Description	A Length	B Width	C Height	D Nos.	E Quantity	F Units	G Total Q
1	RCC Work	Excavation	3.50	3.50	5.00	1.00	61.25	Cft	61.25
2		PCC	3.50	3.50		1.00	12.25	Sft	12.25
3		Footing	3.00	3.00	1.00	1.00	9.00	Cft	9.00
4		RCC Col below PB	1.00	1.00	4.00	1.00	4.00	Sft	4.00
5		Plinth Beam	10.00	1.00	1.00	1.00	10.00	Sft	10.00
6		RCC Col above PB	1.00	1.00	6.50	1.00	6.50	Sft	6.50